



ROBERT B. DOCKING Governor  
DALE E. SAFFELS Chairman  
JULES V. DOTY Commissioner  
JAMES O. GREENLEAF Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. - 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 7 1968  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Dunham of Aspen Drlg. has this

date requested permission to plug the following described well:

Mr. Dunham guarantees payment of the plugging fee.

Operator's full Name: Gary Sandlin

Complete Address: 818 Midland Savings Bldg., Denver, Colo.

Lease Name: Murphy Well No. 1

Location: SE SE NE Sec. 22 Twp. 17 Rge. 19 (E)(W) X

County: Rush Total Depth 4005 Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Dunham was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 850' and displace  
40 sc cement thru drill pipe. Heavy mud to 440' set cementing plug and  
displace 20 sc cement thru drill pipe. Heavy mud to 40' set cementing  
plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plug rat hole with  
2 sc cement.

Very truly yours,

Geo F. Massey  
Conservation Division Agent