

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 6 1967  
9-6-67  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Dunham of Aspen Drlg. has this

date requested permission to plug the following described well:

Mr. Dunham guarantees payment of the plugging fee.

Operator's full Name: Gary Sandlin & So. Texas Dev. Co.

Complete Address: 818 Midland Savings Bldg., Denver, Colo.

Lease Name: Johnson Well No. 1

Location: SE SE SE Sec. 19 Twp. 17 Rge. 19 (E)(W) X

County Rush Total Depth 3955 Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Dunham was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 540' and displace  
80 sc cement with 4% gel, Heavy mud to 330' set cementing plug and  
displace 45 sc cement thru drill pipe. Heavy mud to 40' set cementing  
plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plug rat hole  
with 2 sc cement.

Very truly yours,

Geo. F. Messer  
Conservation Division Agent