

15-165-02200-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

Rush County, Sec. 3 Twp. 18 Rge. 17 (E) W (W)

Location as "NE/CNW/SW" or footage from lines NE SE SW  
Lease Owner Aylward Drilling Co.  
Lease Name Reinhardt #2 Well No. \_\_\_\_\_  
Office Address Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Gas  
Date well completed May 21 19 59  
Application for plugging filed October 13 19 59  
Application for plugging approved October 15 19 59  
Plugging commenced 10-23-59 19 \_\_\_\_\_  
Plugging completed 10-28-59 19 \_\_\_\_\_  
Reason for abandonment of well or producing formation \_\_\_\_\_

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19 \_\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3609 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	1087'	none
				4-1/2"	3609'	3072'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Checked the hole to 3609' and found it open. Filled w/sand to 3570' and dumped 3 sacks of cement with bailer. Pulled 4 1/2" casing to 500' and circulated with 15 sacks of gel mud. Pumped in 20 sacks of cement at 500'. Pulled casing to 170' and pumped in 20 more sacks of cement. Mudded the hole to 40', set rock bridge and ran 10 sacks of cement to base of cellar.

RECEIVED  
STATE CORPORATION COMMISSION

PLUGGING COMPLETED

JAN 21 1960  
1-21-60

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Knight Casing Pulling Co.  
Address Chase, Kansas

STATE OF KANSAS, COUNTY OF RICE, ss.  
I, Noel J. Knight (employee of owner) or (~~WITNESS~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight  
Chase, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of November, 19 59

Thomas V. Duggan  
Notary Public.

My commission expires 9-27-62



*R*  
REINHARDT NO. 2

Casing Record:  
 8 5/8" - 1087'  
 4 1/2" - 3609'

Company: Aylward Drilling Company  
 Contractor: Aylward Drilling Company

Location: NE SE SW  
 Sec. 3-18-17W  
 Rush County, Kansas

Commenced: May 11, 1959  
 Completed: May 20, 1959

Elevation: 2006 R.B.

	<u>From</u>	<u>To</u>	<u>Remarks</u>
Clay & sand	0	300	Set 8/5/8" surface pipe @ 1087' w/450 sacks cement.
Sand & Clay	300	485	
Dakota Sand	485	615	Geological Tops:  Heebner 3248 Toronto 3264 Douglas 3282 Lansing 3300 B/K.C. 3512 Conglomerate 3552 " Sand 3568 Reagan 3596 Granite Wash 3606  DST 3564-3609 Open 30 min. Gas to surf. in 45 Sec., gauged 9 1/2 MCF/15". IBHP 960#/30" - FBHP 960#/30" FP 740#-760#.
Sand & red bed	615	655	
Sand	655	755	
Shale & red bed	755	960	
Red bed & rock	960	1082	
Anhydrite	1082	1125	
Shale & Shells	1125	1500	
Salt	1500	1595	
Shale	1595	1715	
Shale & lime	1715	1850	
Lime	1850	2080	
Sandy lime	2080	2175	
Lime & shale	2175	2410	
Lime	2410	2465	
Shale & lime	2465	3030	
Lime & shale	3030	3240	
Lime	3240	3250	
Lime & shale	3250	3279	
Sandy lime	3279	3000	
Lime	3300	3415	
Lime & Shale	3415	3452	
Lime	3452	3609 T.D.	4 1/2" casing @ 3609' w/100 sax cement.

Completion Data:

Perf. 20 holes - 3585-90  
 32 " - 3593-3601  
 Test 11,404,000 CFGPD

RECEIVED  
 STATE CORPORATION COMMISSION  
 JAN 21 1960  
 1-21-60  
 CONSERVATION DIVISION  
 Wichita, Kansas

I hereby certify that this is a true and correct copy of the above log to the best of my knowledge.

*Paul W. Jesse*

Subscribed and sworn to before me this 30th day of June, 1959.

*Duane Jessup*  
 DUANE JESSUP Notary Public

My commission expires December 11, 1961