

15-165-00149-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Rush County, Sec. 3 Twp. 18 Rge. 17 (E) W (W)

Location as "NE/CNW/SW" or footage from lines NE NE NW

Lease Owner Aylward Drilling Co.

Lease Name Reinhardt #1 Well No.

Office Address Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Gas

Date well completed September 30 1957

Application for plugging filed October 13 1959

Application for plugging approved October 15 1959


Plugging commenced 10-16-59 19

Plugging completed 10-21-59 19

Reason for abandonment of well or producing formation Well went to water

If a producing well is abandoned, date of last production March 1958

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Granite Wash Depth to top 3570 Bottom 3601 Total Depth of Well 3606 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	1085'	none
				5-1/2"	3606'	2878'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked the hole to 3606' and found it open. Filled w/sand to 3550' and dumped 5 sacks of cement with bailer. Pulled 5 1/2" casing to 500' and circulated (20 sacks mud) with mud and pumped in 20 sacks of cement at 500'. Pulled casing to 170' and pumped in 20 more sacks of cement. Pulled rest of casing, cleared hole and mudded the hole to 35', set rock bridge to 30' and ran 10 sacks of cement to base of cellar.

PLUGGING COMPLETED

RECEIVED
STATE CORPORATION COMMISSION

JAN 21 1960

1-21-60
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Knight Casing Pulling Co.

Address Chase, Kansas

STATE OF KANSAS, COUNTY OF RICE, ss.

I, Noel J. Knight (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight

Chase, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 27th day of October, 1959

Thomas V. Duggan Notary Public.

My commission expires 9-27-62



REINHARDT NO. 1

Casing Record:
8 5/8" - 1085'
5 1/2" - 3606'

Company: Aylward Drilling Company et al
Contractor: Aylward Drilling Company

Location: NE NE NW 3-18-17W
Rush County
Kansas

Commenced: September 19, 1957
Completed: September 29, 1957

Elevation: 2008 RB

	<u>From</u>	<u>To</u>	<u>Remarks</u>
Surface Clay & Sand	0	130	Set 8 5/8" surface pipe @ 1085' w/475 sacks cement
Shale & Shells	130	490	
Sand	490	610	Geological Tops:
Shale & Shells	610	650	
Salt	650	715	Cimarron Anhydrite 1078
Shale, Shells & Red Rock	715	790	Heebner Shale 3238
Red Bed w/streaks of Pyrite	790	1000	Toronto Lime 3255
Red Bed & Shells	1000	1078	Douglas Shale 3271
Anhydrite	1078	1115	Lansing/K.C. 3292
Shale & Shells w/salt stk.	1115	1320	Basal K.C. 3511
Red Bed & Shells	1320	1400	Granite Wash 3570
Shale	1400	1790	Pre-Cambrian Granite 3601
Red Bed & Shale	1790	1830	R.T.D. 3606
Lime & Shale	1830	2100	DST 3564-79 Open 70 min. Gas to surf. in 30 seconds, strong blow with fine mud spray. Gauged 4.7 MCFG in 10", 5.8 MCFG in 15", 7.3 MCFG in 30", 45" & 60", 7.9 MCFG in 70". IBHP 1095#/27", FBHP 1095/37", FP 990#-925#.
Lime	2100	2340	
Broken Lime & Shale	2340	2520	DST 3582-98 Open 30 min. Wk. bl. 30 seconds. Rec. 12" fluid, no show or odor. IBHP 80#/30", FBHP 30#/30". FP 0#-0#.
Shale w/lime streaks	2520	2635	
Shale & Lime	2635	3321	Set 5 1/2" casing @ 3606 w/125 sacks cement.
Lime	3321	3450	
Lime & Shale	3450	3579	
Granite Wash	3579	3595	
Conglomerate	3595	3606 T.D.	

RECEIVED
STATE CORPORATION COMMISSION

JAN 21 1968
1-21-68
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that this is a true and correct copy of the above log to the best of my knowledge.

Paul W. Hesse

Subscribed and sworn to before me this 30th day of October, 1957.

Duane Jessup
DUANE JESSUP Notary Public

My commission expires December 11, 1957