

STATE OF KANSAS
STATE CORPORATION COMMISSION


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Rush County. Sec. 3 Twp. 18 Rge. (E) 17 (W)

Location as "NE/CNWxSWx" or footage from lines NW SW NE
Lease Owner: Aylward Drilling Co.
Lease Name: Timken Well No. 1
Office Address: 813 1st Nat'l Bank Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 10-25 19 62
Plugging completed 10-31 19 62
Reason for abandonment of well or producing formation

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Depth to top Bottom Total Depth of Well 3663 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	1072'	none
				4 1/2"	3662'	2604'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Top Perforation 3568'

Sanded hole to 3550' dumped 4 sks cement-
pulled casing to 560'-pumped in 25 sks mud-
pulled 3 more joints-pumped in 20 sks cement-
@ 450'-pulled casing to 170'-pumped in 20 sks
cement-finished pulling casing-capped well with
10 sks cement.

RECEIVED
STATE CORPORATION COMMISSION
11-26-62
NOV 26 1962

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor R & D Casing Pulling Co. License #236
Address Box 572, Hutchinson, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK, ss.
CHARLES D. WILLIAMS (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.
(Signature) Charles D. Williams

SUBSCRIBED AND SWORN TO before me this 20th day of NOVEMBER, 1962

(Address)
DUANE JESSUP Notary Public.
My commission expires DECEMBER 11, 1965

TIMKEN #1

Casing Record:

8 5/8" - 1072'
4 1/2" - 3662 1/2'

Company: Aylward Drilling Company
Contractor: Aylward Drilling Company

Commenced: November 9, 1957
Completed: November 19, 1957

Location: NW SE NE 3-18-17W
Rush County, Kansas

Elevation: 2001' RB

	<u>From</u>	<u>To</u>	<u>Remarks</u>
Surface Clay & Post Rock	0	70	Set 8 5/8" @ 1072' w/450 sax cement
Clay and sand	70	180	
Shale, Shells & Clay	180	440	Geological Tops:
Shale and Clay	440	490	
Dakota Sand	490	605	Climmeron Anhydrite 1067
Shale and Shells	605	645	Topeka Lime 2994
Salt	645	700	Heebner Shale 3240
Shale, Shells & Red Bed	700	835	Toronto Lime 3258
Red Bed & Shells	835	1067	Douglas Shale 3273
Anhydrite	1067	1097	Lansing/K.C. 3294
Shale & Shells	1097	1250	Basal K.C. 3512
Shale with Lime	1250	1610	Conglomerate 3568
Shale with Lime Streaks	1610	1885	Basalt or Schist 3618
Lime, Sand & Shale	1885	2020	Granite Wash 3653
Lime	2020	2090	R.T.D. 3663
Lime & Shale	2090	2500	
Broken Lime & Shale	2500	2630	DST 3549-3663 Misrun
Shale & Lime Streaks	2630	2795	
Shale & Lime	2795	2985	
Lime & Shale	2985	3350	DST 3521-3663 Open 75 min. Gas to
Lime	3350	3419	surface in 1 1/2 min., heavy mud spray for
Lime & Shale	3419	3464	40 min. Gauged 7,000 MCF in 45 min.,
Shale & Lime Lime	3464	3512	6,500 MCF in 50 min., 5,700 MCF in 60",
Shale & Lime	3512	3560	5,500 MCF in 70 min., 5,500 MCF in 75".
Lime & Shale	3560	3568	Rec. 10" sl. GCM, no water or oil.
Conglomerate	3568	3615	ISIP 1055#, FBHP 1070/30", FP 645#-925#
Shale	3615	3653	
Granite Wash	3653	3663 T.D.	Set 4 1/2" @ 3662 1/2' w/125 sax cement.

RECEIVED
STATE CORPORATION COMMISSION
11-26-62
NOV 26 1962
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that this is a true and correct copy of the above log to the best of my knowledge.

Paul W. Hesse

Subscribed and sworn to before me this 29th day of November, 1957.

Duane Jessup
DUANE JESSUP Notary Public

My commission expires December 11, 1957