

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Rush County, Sec. 2 Twp. 18 Rge. 17 (E) (W)

Location as "NE/CNW%SW%" or footage from lines C-NW-NW
Lease Owner Aylward Drilling Company
Lease Name Robison Well No. 1
Office Address 813 First Nat'l Bldg., Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed January 3 19 59
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced March 18 19 63
Plugging completed March 19 19 63
Reason for abandonment of well or producing formation

NORTH

Section Plat grid with 'X' in the top-left cell.

Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Depth to top Bottom Total Depth of Well 3588 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Table with columns: FORMATION, CONTENT, FROM, TO, SIZE, PUT IN, PULLED OUT. Contains two rows of casing data.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Dumped 25 sacks plug to bottom, top of cement at 3249 feet.

Mix and circulated mud and jell and spotted 25 sacks cement at 435 feet. Spotted 25 sacks cement at 180 feet, Spotted 5 sacks cement at 25 feet.

RECEIVED
STATE CORPORATION COMMISSION

APR 1 1963

CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor Kent Well Servicing Company
Address Box 470, El Dorado, Kansas

STATE OF Kansas, COUNTY OF Butler, ss.
(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Mary Payne

(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of March, 19 63

My commission expires June 18, 1963

Ethelene E. Phillips
Notary Public.



Robison #1

Casing Record: Company: Aylward Drilling Company et al Location: C NW NW
 8 5/8" - 1083' Commenced: December 20, 1958 Section: 2-18-17W
 4 1/2" - 3588' Completed: January 3, 1959 Rush County
 Kansas

Elevation - 2009' R.B.

	<u>From</u>	<u>To</u>	<u>Remarks</u>
Clay & Sand	0	285	Set 8 5/8" surface pipe at 1083"
Sand & Shale	285	380	w/450 sacks cement.
Shale & Clay	380	485	
Sand	485	605	Geological Tops:
Red bed & Shale	605	635	Anhydrite 1075
Shale Shells Red Rock	635	715	Topeka 2998
Red Rock Shale & Pyrite	715	905	Heebner 3244
Red Rock & Shale	905	1060	Toronto 3263
Chalk	1060	1075	Lansing K.C. 3298
Anhydrite	1075	1110	Base K.C. 3515
Shale & Shells	1110	1470	Conglomerate Sand 3556
Salt	1470	1550	Conglomerate Grav. 3570
Shale	1550	1800	Pre-Cambrian Schist
Lime & Shale	1800	2080	and Wash 3579
Lime	2080	2335	
Lime & Shale	2335	2725	
Shale & Lime	2725	2950	
Lime & Shale	2950	3305	DST 3553-3588 Open 18". Very strong
Lime	3305	3588 T.D.	immediately, blow. Rec. 2" muddy water. IFP: 835# FBHP 960#/30"

4 1/2" at 3588' w/50 sacks cement

RECEIVED
STATE CORPORATION COMMISSION

APR 25 1963

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that this is a true and correct copy of the above log to the best of my knowledge.

Paul W. Jesse

Subscribed and sworn to before me this 9th day of March, 1959.

Duane Jessup
DUANE JESSUP

My commission expires December 11, 1961.