


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Rush County, Sec. 32 Twp. 18 Rge. 16 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
SE NW NW

Lease Owner Raymond Oil Company, Inc.
Lease Name HANHARDT Well No. 1
Office Address 200 West Douglas, Wichita, Ks. 67202
Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole



Locate well correctly on above
Section Plat

Date Well completed December 1 19 79
Application for plugging filed Dec. 1 19 79
Application for plugging approved Dec. 1 19 79
Plugging commenced Dec. 1 19 79
Plugging completed Dec. 1 19 79
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Marion Schmidt
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3835'
Show depth and thickness of all water, oil and gas formations.


OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Bottom Plug @ 600' with 70 sacks 50/50 pozmix, 4% Gel thru drill pipe
Top Plug @ 40' with $\frac{1}{2}$ sack hulls for solid bridge & 10 sacks cement
5 sacks cement in rat hole



(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Duke Drilling Co., Inc.

STATE OF Kansas COUNTY OF Barton, ss.

Bill Draney (employee of owner) or ~~(owner or operator)~~
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bill Draney
Box 823 - Great Bend, Ks. 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 4th day of December, 19 79

Dorothy M. Hoque
Notary Public.

My commission expires 4-11-1982

DRILLERS' WELL LOG

DATE COMMENCED: November 23, 1979

Raymond Oil Company, Inc.

DATE COMPLETED: Dec. 1, 1979

HANHARDT # 1
SE NW NW
Sec 32-T 18S-R16W
Rush County, KansasELEVATION:FORMATION DATA

Anhydrite	1122
Topeka	3102
Heebner	3354
Toronto	3373
Douglas	3387
Lansing-K.C.	3411
Base-K.C.	3678
Conglomerate Sand	3739
Granite Wash	3784
RTD	3835

SURFACE PIPE: Set new
20 #, 8-5/8" pipe at
1126' w/425 sacks 60/40
pozmix, 2% gel, 3% cc.

0 - 38'	Surface Soil, Post Rock
38 - 521'	Rock & Shale
521 - 671'	Sand
671 - 1122'	Shale - Red Bed
1122 - 1156'	Anhydrite
1156 - 2830'	Shale & Lime
2830 - 3102'	Lime & Shale
3102 - 3354'	Lime
3354 - 3358'	Shale
3358 - 3373'	Lime & Shale
3373 - 3387'	Lime
3387 - 3411'	Shale
3411 - 3678'	Lime
3678 - 3784'	Lime, Shale, Sand
3784 - 3835'	Granite Wash, Lime
3835	RTD

A F F I D A V I T

State of Kansas
County of Barton) ss

ELLI Draney, of lawful age does swear and state that the facts and
statements herein contained are true and correct to the best of his knowledge.

Subscribed and sworn to before me this 4th day of December 1979

Bill Draney
Notary Public

My Comm. Expires: April 11, 1982