

15-165-01806-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Rush County, Sec. 25 Twp. 18S Rge. 16 ~~XX~~ (W)

Location as "NE/CNW/SW" or footage from lines N/2 S/2 SW/4
Lease Owner Clark Knight Drilling Co., Inc.
Lease Name Hergert Well No. 1
Office Address P.O. Box 162 - Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed 2-7 19 58
Application for plugging filed 2-11 19 58
Application for plugging approved Yes 19 58
Plugging commenced 2-13 19 58
Plugging completed 2-18 19 58
Reason for abandonment of well or producing formation Non - commercial

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well _____
Producing formation Reagan Sand Depth to top 3546 Bottom 3566 Total Depth of Well 3566 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	985'	None
				5 1/2	3,555'	3,255'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with sand from 3,566' to 3,540' and five sack cement from 3,540' to 3,515'
Mudded from 3,515' to 400'
Rock bridge from 400' to 390'
25 sack cement from 390' to 315'
Mudded from 315' to 200'
Rock bridge from 200' to 190' 25 sack cement to 115'
Mud from 115' to 30' 10 sack cement to bottom of cellar

RECEIVED
STATE CORPORATION COMMISSION
MAR 11 1958
3-11-58
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Glenn and Smith
Address Ellinwood, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
L. C. Knight (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
P.O. Box 162 - Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 3rd day of March, 19 58

My commission expires April 1, 1959
Ulanda Nichols Notary Public.

PLUGGING
FILE 859 25118 R.16.4
BOOK PAGE 82 LINE 11

Company: Clark Knight Drilling Co., Inc.
 Farm: Hergert No. 1

Sec. 25-18S-16W
 C N/2 S/2 SW

County Rush
 Kansas

Total Depth, 3559'
 Comm. 1-20-58 Comp. 1-31-58
 Shot or Treated.
 Contractor: Ari-Kan Drilling Company
 Issued.

Elev. 1950 DF
 1952 RB

Production.

Casing:

8" cemented at 985'
 5 1/2" cemented at 3556

Figures indicate bottom of formation:

Surface clay and sand	50
Shale and shells	410
Sand	510
Shale and sand Stks	580
Shale and shells & Red Bed	870
Shale, Shells and Red Bed	979
Anhydrite	986
"	1016
Shale and Shells	1205
Shale and Shells	1545
Shale and Lime	1765
Lime	1895
Lime and Shale	2025
Lime	2100
Lime	2180
Lime and Shale	2260
Lime and Shale	2370
Lime	2465
Lime and Shale	2575
Shale and Lime	2710
Lime and Shale	2815
Lime and shale	2920
Shale and Lime	2940
Lime	3005
Lime	3095
Lime	3238
Lime and Shale	3313
Lime	3546
Sand	3559
TD	3559

Tops:

Heebner	3193
Toronto	3210
Lansing	3261
Base KC	3480
Conglomerate	3527
Reagan Sand	3546
TD	3559

IRVING COUNTY
 STATE OF KANSAS COMMISSIONER

2-13-58

FEB 13 1958

COMMISSION DIVISION
 Topeka, Kansas

PLUGGING
 SEC 25-18S-16W
 BOOK PAGE 82 LINE 11