

15-165-02152-0000


TC

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Rush County, Sec. 25 Twp. 18 Rge. 16 (E) (W)  
Location as "NE/CNW/SW" or footage from lines SW SE  
Lease Owner Northern Natural Gas Company  
Lease Name J. C. Giesick NN #190-1, Well No. # 4  
Office Address  
Character of Well (completed as Oil, Gas or Dry Hole)  
Date well completed 19  
Application for plugging filed 5-2-61 19  
Application for plugging approved 5-11-61 19  
Plugging commenced 5-10-61 19  
Plugging completed 5-23-61 19  
Reason for abandonment of well or producing formation



If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation Depth to top Bottom Total Depth of Well 3585' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				12 1/2"	225'	none
				8 5/8"	995'	none
12 1/2" & 8 5/8"	left in hole and were cemented to surface.			5 1/2"	3570'	2176'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugging commenced 5-10-61. Plugging completed 5-23-61.  
Plugged off bottom: Sanded back to 3560' and dumped 5 sacks cement.  
Worked and shot 5 1/2" casing free at 2176'. Built rack and slide.  
Pulled and layed down casing.  
Plugged well: Filled hole with heavy mud. Squeezed the well with 40 sacks of mud and 100 sacks of cement. Recapped well to bottom of cellar with 5 sacks of cement.

RECEIVED  
STATE CORPORATION COMMISSION  
7-12-61  
JUL 12 1961

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Forbes Casing Pulling, Inc. CONSERVATION DIVISION  
Address P. O. Box 221 Great Bend, Kansas Wichita, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
J. O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. O. Forbes  
Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 5th day of July, 1961

Kayann Jenkins  
Notary Public

My commission expires December 8th, 1963




KENWOOD OIL CO.  
 Giosick No. 4

SEC. 25 T. 18 R. 16W.  
 SW<sup>6</sup> SE

Total Depth, 3505  
 Corn. 9-7-41 Comp. 10-2-41  
 Shot or Treated.  
 Contractor.  
 Issued. 11-1-41

County Rush.



CASING.

12 $\frac{1}{2}$ " 225' cemented.  
 8 $\frac{5}{8}$ " 995.31' cemented.  
 5 $\frac{1}{2}$ " 3570' cemented.

Elevation.

Production. Pot. 265 B.

Figures Indicate Bottom of Permeables.

shale and sand shells	230
shale	302
pyrite and shale	315
shale	325
shale and pyrite	415
sand	510
shale	543
sand and shale	635
shale	703
shale and red beds	915
red beds	972
anhydrite	1000
red beds and shells	1190
shale and lime shells	1375
shale and shells	1400
salt and shells	1535
shale and shells	1730
broken lime	1630
lime	1655
broken lime	1905
lime and shale	2050
broken lime	2105
lime	2395
shale and shells	2495
shale	2605
broken lime	2625
shale	2655
shale and shells	2763
shale	2795
lime	2842
broken lime	2875
lime	3105
K.C. lime	3190
lime	3541
conglomerate	3560
oring 3560	
conglomerate and sand	3570
Reagan sand	3505
Total Depth.	