

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Rush

County. Sec. 25 Twp. 18S Rge. (E) 16 (W)

Location as "NE/CNW/SW" or footage from lines CSL SE/4

Lease Owner NORTHERN NATURAL GAS COMPANY

Lease Name Giesick (also know as Unit 190-3) Well No. 3

Office Address 1209 Williams, Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil Well

Date well completed a June 27 19 55

Application for plugging filed yes 19

Application for plugging approved yes 19


Plugging commenced December 19 19 59

Plugging completed December 23 19 59

Reason for abandonment of well or producing formation depleted

If a producing well is abandoned, date of last production March 28 19 59

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Depth to top Bottom Total Depth of Well 3575 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				13-3/8"	269'	None
				8-5/8"	992'	None
				5-1/2"	3575'	2019'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugging commenced 12-19-59. Measured into total depth. Worked and shot pipe. Shot 5 1/2" casing at 2019', pulled and layed down casing. Cement with 85 sx Type 3 SR cement from 3575 to 2900'; mud from 2900 to 2100'; cemented with 317 sx Type 3 SR cement and 102 sx Diacel "D" from 2100 to 0'.

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 30 1959  
12-30-59  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor J. O. Forbes d/h/a Forbes Casing Pulling Co.  
Address Box 221, Great Bend, Kansas

STATE OF KANSAS COUNTY OF BARTON ss.  
Orlin G. Stearns (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Orlin G. Stearns  
1209 Williams, Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 29th day of December 19 59

Dorothy B. John Notary Public.

My commission expires June 18, 1963


COPY

SCHERMERHORN-WINTON COMPANY.  
 Giesiok No. 3

SEC. 25 T. 18 R. 16W.  
 CSL SE

Total Depth. 3575  
 Comm. 12-11-40 Comp. 1-22-41  
 Shot or Treated.  
 Contractor.  
 Issued. 2-6-41

County Rush.



CASING.

13"	269.86	cemented
85/8"	992.50	cemented.
5 1/8"	3598.08	cemented.

Elevation.

Production. Pct. 178 B.

Figures Indicate Bottom of Formations.

clay and sand rock	40
shale and sand	180
shale and shells	237
shale	320
lime	335
shale and shells	410
sand	510
red bed	542
sand	580
red bed	976
anhydrite	1004
red bed shale and shells	1251
red bed	1425
salt	1500
salt and shale	1680
shale and shells	1763
shale	1785
broken lime	2045
lime	2100
shy lime & shale	2198
lime	2290
broken lime	2350
broken lime	2375
shale	2695
broken lime	2802
lime	2980
Topeka lime	3033
lime	3280
shale and lime	3310
K.C. Line	3364
soft no show oil	3380
lime	3440
lime with streaks of shale	3512
lime and shale	3550
conglomerate oored	3552
conglomerate lime	3560
sand	3567
sand	3575
Total Depth.	