

15-165-20971-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

RECEIVED

Form CP-4
Rev. 12-15-80

2-2-82
FEB - 2 1982

WELL PLUGGING RECORD

CONSERVATION DIVISION
Wichita, Kansas

Give All Information Completely
Make Required Affidavit

COUNTY Rush SEC. 25 TWP. 18 RGE. 16 E/W
Location as in quarters or footage from lines:

SW NW SE

Lease Owner Sunflower Oil Co.
 Lease Name GISICK Well No. #1
 Office Address 2048 South Emporia Wichita, KS 67211
 Character of Well (Completed as Oil, Gas or Dry Hole):
 Date Well Completed 1-25-82
 Application for plugging filed 1-25-82
 Plugging commenced 1-25-82
 Plugging completed 1-25-82
 Reason for abandonment of well or producing formation _____

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Steve Durrant
 Producing formation _____ Depth to top _____ bottom _____ T.D. 3535'
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Bottom Plug: @ 900' w/70 sacks cement thru drill pipe
Middle Plug: @ 420' w/40 " " " " "
Top Plug: @ 40' w/10 sacks cement bridged & plug
5 sacks in Rat Hole

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Lobo Drilling Co.

STATE OF Kansas COUNTY OF Barton, ss.
Ervin Neighbors (employee of owner) or (~~owner or operator~~) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) Ervin Neighbors
Box 877 Great Bend, KS 67530
 (Address)

SUBSCRIBED AND SWORN TO before me this 29 day of January, 1982
Deirdre M. Hague
 Notary Public.

My Commission expires: 4-11-1982

DRILLERS' WELL LOG

DATE COMMENCED: January 19, 1982
 DATE COMPLETED: January 23, 1982

Sunflower Oil Co.
 GISICK #1
 SW NW NE
 Sec. 25, T18S, R16W
 Rush County, Ka.

0 - 90' Surface Soil, Shale
 90 - 944' Shale, Sand Streaks
 944 - 961' Anhydrite
 961 - 3170' Shale & Lime
 3170 - 3187' Lime
 3187 - 3222' Shale
 3222 - 3236' Lime & Shale
 3236 - 3470' Lime
 3470 - 3513' Shale, Lime, Chert
 3513 - 3535' Shale & Sand
 3535' RTD

ELEVATION: 1936 K.B.

FORMATION DATA

Anhydrite	944'
Maebner	3160'
Toronto	3170'
Douglas	3187'
Br. Lime	3222'
Lansing K.C.	3236'
Base K.C.	3470'
Conglomerate	3480'
Regan	3513'
RTD	3535'

RECEIVED
 STATE CORPORATION COMMISSION
 2-2-82
 FEB - 2 1982
 CONSERVATION DIVISION
 Wichita, Kansas

Surface Pipe: Set new 8-5/8".
 20' pipe @951' w/450 sacks
 60/40 poamix, 2% gel 3% cc.

A F F I D A V I T

STATE OF KANSAS
 COUNTY OF BARTON) ss

Ervin Neighbors of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

Ervin Neighbors

Subscribed and sworn to before me this 26 day of January 1982.

My Comm. Expires:

4-11-1982

Dorothy M Hague
 Notary Public