

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY RUSH SEC. 25 TWP. 18 RGE. 16w E/W
 Location as in quarters or footage from lines:

825' FEL 100' FSL OF SE/4

Lease Owner ALLEN DRILLING CO.

Lease Name GIESICK-SCHROEDER Well No. 1

Office Address 1105 WALNUT; P.O. BOX 1389; GREAT BEND, KS. 67530

Character of Well (Completed as Oil, Gas or Dry Hole): OIL

Date Well Completed 3-4-83

Application for plugging filed 2-26-83

Plugging commenced 3-1-83

Plugging completed 3-4-83

Reason for abandonment of well or producing formation DRY

Locate Well
 correctly on above
 Section Platt.

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well STEVE DURRANT

Producing formation _____ Depth to top _____ bottom _____ T.D. 3591'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				4 1/2"		2,922.35'

Describe in detail the manner in which the well was plugged, indicating where the mud
 fluid was placed and the method or methods used in introducing it into the hold. If cement
 or other plugs were used, state the character of same and depth placed, from _____ feet
 to _____ feet for each plug set.

SET PLUG AND SAND BACK TO 3,540' WITH 4 SACKS OF CEMENT

ALLIED CAME OUT AND PUMPED DOWN 2 SACKS OF HULLS; 10 SACKS OF LELL; 70 SACKS OF CEMENT
15 SACKS OF JELL; 1 SACK OF HULLS; RUBBER PLUG; AND 150 SACKS OF CEMENT 50/50 POZ MIX
2% JELL 3% C.C.

(If additional description is necessary, use BACK of this sheet)
 Name of Plugging Contractor H.H. CASING PULLING CO.


RECEIVED
 STATE CORPORATION COMMISSION
3-17-83
MAR 17 1983

STATE OF KANSAS COUNTY OF RENO, ss.
 CONSERVATION DIVISION
 Wichita, Kansas

DONALD H. HURST (employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) Donald H. Hurst
 2900 ACRES RD. APT. 107; HUTCHINSON, KS. 67501
 (Address)

SUBSCRIBED AND SWORN to this 14 day of MARCH, 19 83



Madeline Hurst
 Notary Public.

My Commission expires: _____

GIESICK-SCHROEDER No. 1

825' FEL & 100' FSL of SE/4 Sec. 25-18S-16W

Rush County, Kansas

API# 15-165-20,928

Spudded: 10/5/81

Completed: 10/10/81

Surface: 8 5/8" 20# @ 1008'

w/425 sks 50/50 poz, 2% gel & 3% cc

Production: 4 1/2" 10.5# @ 3588'

w/ 100 sks 50/50 poz, 18% salt & 3/4% CFR2

TD: 3591'

Perfs: OH 3591-97'

GIESICK-SCHROEDER Twin (SWD)

150' W C NE NE Sec. 36-18S-16W

Rush County, KS

API# 15-165-20,235-A 535'A

Spudded: 4/10/82

Completed: 4/13/82

Surface: 8-5/8" @ 715' - Washdown

Production: 5 1/2" 17# @ 3646'

w/200 sks Lite & 50 sks 50/50 poz, 2% gel

TD: 3910'

OH: 3646-3910'

Perfs @ 3611-16 squeezed

3405-11 squeezed

1000' - circulated cement to surface w/300 sks

RECEIVED
STATE CORPORATION COMMISSION
FEB 28 1983
2-28-83
CONSERVATION DIVISION
Wichita, Kansas

15-165-20928-0000

ALLEN DRILLING CO
 P.O. BOX 1389 #1 GIESEK-SCHROEDER 25-18-16W
 GREAT BEND, KS 67530 100' FSL &
 CONTR ALLEN DRILLING CO CTY RUSH 825' FEL, SE/4
 GEOL ROBERT DOUGHERTY FIELD OTIS ALBERT

1993 KB CN 10/5/81 CARD ISSUED 7/29/82 OIL WELL
 1988 GL FORM & INTV NA
 API 15-165-20,928

+	+	+
+	+	+
+	+	+

SMP	TOPS	DEPTH	DATUM
ANN		996	+ 997
B ANH		1030	+ 963
HEEB		3234	-1241
YOR		3245	-1252
DOUG		3263	-1270
BR LM		3299	-1306
LANS		3317	-1324
B KC		3535	-1542
CHER SH		3564	-1571
SPRS		3571	-1578
REAR SD		3585	-1592
RTD		3591	-1598

8 5/8" 1008/425sx; 4 1/2" 3588/100sx
 NO DSTS
 MICT - CO, PF (FORM & INTV NA), TSTD,
 POP, OIL WELL - NO OTHER INFO TO BE
 RELEASED AT PRESENT - WILL RELEASE
 INFO WHEN AVAILABLE - TEMP COMP
 7/29/82

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

RECEIVED
 STATE CORPORATION COMMISSION
 FEB 28 1983
 2-28-83
 CONSERVATION DIVISION
 Wichita, Kansas