

SIDE ONE

Two (2) copies of this form shall be filed with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within thirty (30) days after the completion of a well, regardless of how the well was completed.

Attach separate letter of request if the information is to be held confidential. If confidential, only file one copy. Information on Side One will be of public record and Side Two will then be held confidential.

Applications must be made on dual completion, commingling, salt water disposal, injection and temporarily abandoned wells.

Attach one copy only wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.). (Rules 82-2-105 & 82-2-125) KCC# (316) 263-3238.

LICENSE # 6883 EXPIRATION DATE June 30, 1983

OPERATOR Robinowitz Oil Company APT NO. 15-077-20,847-20855-0000

ADDRESS 6650 South Lewis COUNTY Harper

Tulsa, Oklahoma 74136 FIELD Runnymede

\*\* CONTACT PERSON Charles Son PROD. FORMATION -----

PHONE (918) 494-4034

PURCHASER LEASE Stuckey

ADDRESS WELL NO. #1

DRILLING Rains & Williamson Oil Co., Inc. WELL LOCATION SW SW NE NW

CONTRACTOR ADDRESS 435 Page Court, 220 W. Douglas 1155 Ft. from N Line and

Wichita, Kansas 67202 1485 Ft. from W Line of

the NW (Qtr.) SEC 26 TWP 31S RGE 6W.

PLUGGING Same WELL PLAT (Office Use Only)

CONTRACTOR ADDRESS KCC [check]

ADDRESS KGS [check]

TOTAL DEPTH 4700' PBSD SWD/REP

SPUD DATE 11-10-82 DATE COMPLETED 11-19-82 PLG.

ELEV: GR 1396' DF KB 1405'

DRILLED WITH (CABLE) (ROTARY) (AIR) TOOLS.

DOCKET NO. OF DISPOSAL OR REPRESSURING WELL BEING USED TO DISPOSE OF WATER FROM THIS LEASE

Amount of surface pipe set and cemented 314' DV Tool Used?

THIS AFFIDAVIT APPLIES TO: (Circle ONE) - Oil, Gas, Shut-in Gas, (Dry) Disposal, Injection, Temporarily Abandoned, OWWO. Other

ALL REQUIREMENTS OF THE STATUTES, RULES AND REGULATIONS PROMULGATED TO REGULATE THE OIL AND GAS INDUSTRY HAVE BEEN FULLY COMPLIED WITH.

A F F I D A V I T

Charles E. Son, being of lawful age, hereby certifies that:

I am the Affiant, and I am familiar with the contents of the foregoing Affidavit. The statements and allegations contained therein are true and correct.

Charles E. Son (Name)

SUBSCRIBED AND SWORN TO BEFORE ME this 10th day of December, 1982.

(NOTARY PUBLIC)

MY COMMISSION EXPIRES: March 13, 1985

\*\* The person who can be reached by phone regarding any questions concerning this information.

RECEIVED STATE CORPORATION COMMISSION DEC 15 1982 12-13-82 CONSERVATION DIVISION Wichita Kansas

FILL IN WELL LOG AS REQUIRED:

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.			SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.	
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
No Cores - No Tests			Tarkio Limestone	2412
			Topeka Limestone	2737
			Oread Limestone	3015
			Heebner Shale	3066 ✓
			Douglas Shale	3158
			Stalnaker Sand	3396
			Base of Stalnaker	3482
			Kansas City Group	3640 ✓
			Base of Kansas City	3864
			Marmaton	3920
			Cherokee Shale	4074
			Mississippi	4246 ✓
		Kinderhook Shale	4554 ✓	
		Simpson Sand	4676 ✓	
		Total Depth	4700	

Report of all strings set— surface, intermediate, production, etc. CASING RECORD (New) or (Used)

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Socks	Type and percent additives
Surface	12 1/4"	8 5/8"	24#	314'	Common	250 sx.	2% gel, 3% cc.

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Socks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Porter set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Cement to plug: 30 sx @ 750', 30 sx @ 220', 20 sx @ 60', 10 sx in rat hole	

Date of first production	Producing method (flowing, pumping, gas lift, etc.)	Gravity
Dry		
RATE OF PRODUCTION PER 24 HOURS	Oil Gas Water	% Gas-oil ratio
Disposition of gas (vented, used on lease or sold)	MCF	BSls. CFPB
	Perforations	