

STATE CORPORATION COMMISSION OF KANSAS
OIL & GAS CONSERVATION DIVISION
WELL COMPLETION FORM
ACO-1 WELL HISTORY
DESCRIPTION OF WELL AND LEASE

API NO. 15- 077-213650000

ORIGINAL

County Harper

C - NW - NW - SW Sec. 1 Twp. 31S Rge. 7 XX^E_W

2310 Feet from (S)N (circle one) Line of Section

330 Feet from E(W) (circle one) Line of Section

Footages Calculated from Nearest Outside Section Corner:
NE, SE, NW or (SW) (circle one)

Lease Name Kelly Well # 1

Field Name Maple Grove South

Producing Formation Mississippi

Elevation: Ground 1577 KB 1587

Total Depth 4450 PBTD 4408

Amount of Surface Pipe Set and Cemented at 224 Feet

Multiple Stage Cementing Collar Used? Yes X No

If yes, show depth set _____ Feet

If Alternate II completion, cement circulated from 230

feet depth to surface w/ 200 sx cmt.

Drilling Fluid Management Plan AH-1-1-21-99 UIC
(Data must be collected from the Reserve Pit)

Chloride content 9000 ppm Fluid volume 320 bbls

Dewatering method used settlement

Location of fluid disposal if hauled offsite:

Operator Name MESSENGER PETROLEUM, INC.

Lease Name Nicholas License No. 4706

NE Quarter Sec. 20 Twp. 30 S Rng. 8 (EW)

County Kingman Docket No. D-25,073

Operator: License # 4706

Name: MESSENGER PETROLEUM, INC.

Address 1015 East Hwy 54

City/State/Zip Kingman, Ks. 67068

Purchaser: Peoples/Equiva

Operator Contact Person: Jon F. Messenger

Phone (316) 532-5400

Contractor: Name: Sterling Drilling Co.

License: 5142

Wellsite Geologist: Jon F. Messenger

Designate Type of Completion
 New Well Re-Entry Workover

Oil SWD SIGW Temp. Abd.
 Gas ENHR SIGW
 Dry Other (Core, WSW, Expl., Cathodic, etc)

If Workover:

Operator: _____

Well Name: _____

Comp. Date _____ Old Total Depth _____

Deepening Re-perf. Conv. to Inj/SWD
 Plug Back PBTD
 Commingled Docket No. _____
 Dual Completion Docket No. _____
 Other (SWD or Inj?) Docket No. _____

09-09-98 09-16-98 10-13-98
Spud Date Date Reached TD Completion Date

INSTRUCTIONS: An original and two copies of this form shall be filed with the Kansas Corporation Commission, 130 S. Market - Room 2078, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information on side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.


Signature Jon F. Messenger

Title President/Geologist Date 1-5-98

Subscribed and sworn to before me this 5th day of JANUARY, 19 99.

Notary Public John M. Wood

Date Commission Expires _____



K.C.C. OFFICE USE ONLY
F Letter of Confidentiality Attached
C Wireline Log Received
C Geologist Report Received
Distribution
 KCC SMD/Rep NGA
 KGS Plug Other (Specify)

Form ACO-1 (7-91)

ORIGINAL

15-077-21365-0000
ALLIED CEMENTING CO., INC. 9789

Federal Tax I.D.# 48-0727860

TO P.O. BOX 31
 RUSSELL, KANSAS 67665

ORIGINAL SERVICE POINT:
 Medicine Lodge

DATE <u>9-9-98</u>	SEC. <u>1</u>	TWP. <u>31s</u>	RANGE <u>7w</u>	CALLED OUT <u>8:00 Am</u>	ON LOCATION <u>9:30 Am</u>	JOB START <u>12:30</u>	JOB FINISH <u>12:45</u>
LEASE <u>Kelly</u>		WELL # <u>1</u>		LOCATION <u>Duquoin Elevator</u>		COUNTY <u>Harper</u>	STATE <u>Kansas</u>
OLD OR <u>NEW</u> (Circle one)				<u>2 1/2 E, 1/2 S, 1/2 W, 7/8</u>			

CONTRACTOR Sterling
 TYPE OF JOB surface
 HOLE SIZE 12 1/4 T.D. 230
 CASING SIZE 8 1/2 x 20" DEPTH 227
 TUBING SIZE _____ DEPTH _____
 DRILL PIPE _____ DEPTH _____
 TOOL _____ DEPTH _____
 PRES. MAX 250 MINIMUM 100
 MEAS. LINE _____ SHOE JOINT _____
 CEMENT LEFT IN CSG. 15 feet
 PERFS. _____
 DISPLACEMENT 13.75

OWNER Messenger Petroleum
 CEMENT AMOUNT ORDERED 200.5x 60:40:2+3 1/2 cc

EQUIPMENT

PUMP TRUCK CEMENTER Carl Balding
 # 255-265 HELPER Shane Winsor
 BULK TRUCK
 # 256-239 DRIVER James Holt
 BULK TRUCK
 # _____ DRIVER _____

COMMON	<u>120</u>	@	<u>6.35</u>	<u>762.00</u>
POZMIX	<u>80</u>	@	<u>3.25</u>	<u>260.00</u>
GEL	<u>3</u>	@	<u>9.50</u>	<u>28.50</u>
CHLORIDE	<u>6</u>	@	<u>28.00</u>	<u>168.00</u>
		@		
		@		
		@		
		@		
		@		
HANDLING	<u>200</u>	@	<u>1.05</u>	<u>210.00</u>
MILEAGE	<u>200 x 45</u>	@	<u>.04</u>	<u>360.00</u>

TOTAL \$1788.50

REMARKS:

Pipe on bottom, break circulation w/ Big pump.
Run 28 Bbls freshwater mix + pump 200.5x 60:40:2+3 1/2 cc
Cement in stop pumps, switch valves + release plug
Displace w/ 13.75 Bbls freshwater.
Cement did circulate shut IN. ✓

SERVICE

DEPTH OF JOB	<u>227</u>			
PUMP TRUCK CHARGE	<u>0-300'</u>			<u>470.00</u>
EXTRA FOOTAGE		@		
MILEAGE	<u>45</u>	@	<u>2.95</u>	<u>132.25</u>
PLUG	<u>wooden 8 1/8"</u>	@	<u>45.00</u>	<u>45.00</u>
		@		
		@		

TOTAL \$643.25

CHARGE TO: Messenger Petroleum
 STREET 1015 E. Hwy. 54
 CITY KEENEMAN STATE KANSAS ZIP 67068

FLOAT EQUIPMENT

RECEIVED
 STATE COMMISSION
 JAN 5 1999
 CONSERVATION DIVISION
 Wichita, Kansas

TOTAL _____

TAX _____
 TOTAL CHARGE 2431.75
 DISCOUNT 364.76 IF PAID IN 30 DAYS
 NET # 2066.99

SIGNATURE V. Thompson
 PRINTED NAME V. Thompson

To Allied Cementing Co., Inc.
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

15-077-2365-0000

ALLIED CEMENTING CO., INC. 2536

ORIGINAL SERVICE POINT: St Bend

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

DATE <u>9-16-98</u>	SEC: <u>1</u>	TWP. <u>31</u>	RANGE <u>7</u>	CALLED OUT <u>4:00AM</u>	ON LOCATION <u>9:00AM</u>	JOB START <u>2:10PM</u>	JOB FINISH <u>3:30PM</u>
LEASE <u>Kelly</u>	WELL # <u>1</u>	LOCATION <u>Duquoin - 2 1/2 E, 1/2 S, 1/4 W</u>			COUNTY <u>Harper</u>	STATE <u>Ka</u>	

CONTRACTOR Starling Dalg

TYPE OF JOB Production

HOLE SIZE 7 7/8" T.D. 4450'

CASING SIZE 5 1/2" DEPTH 4445'

TUBING SIZE DEPTH

DRILL PIPE DEPTH

TOOL DEPTH

PRES. MAX 1000 # MINIMUM 300 #

MEAS. LINE SHOE JOINT 29'

CEMENT LEFT IN CSG. 29'

REMARKS: Displacement = 105 1/4 bbls.

OWNER Same CEMENT

AMOUNT ORDERED 125 bbls ASC 5# Kolor/br
25 bbls 6 7/8" 4 1/2" ad.
500 gal Mud Clean

COMMON @

POZMIX @

GEL @

CHLORIDE @

HANDLING @

MILEAGE @

EQUIPMENT

PUMP TRUCK CEMENTER Tom D

181 HELPER Bob B

BULK TRUCK DRIVER John K

257-314

BULK TRUCK DRIVER

TOTAL _____

REMARKS:

Ran 4445' of 5 1/2" cas. Brake circulation.
Pumped 500 gal Mud Clean followed by
125 bbls ASC-5# Kolor/br. Mixed and
clean of cement. Displaced with fresh
water. Banded plug at 1000 #. Released
and held.

Plugged bathole w/ 15 bbls 6 7/8" 4 1/2" - Main hole w/ 10 bbls 6 7/8" 4 1/2"

SERVICE

DEPTH OF JOB 4445'

PUMP TRUCK CHARGE _____

EXTRA FOOTAGE @ _____

MILEAGE @ _____

PLUG 1 1/2" Rubber @ _____

TOTAL _____

CHARGE TO: Messenger Petroleum, Inc

STREET 1015 East Hwy 54

CITY Kingman STATE Ka ZIP 67068

FLOAT EQUIPMENT

STATE CONSTRUCTION COMMISSION

1-5 1/2" Guide Shoe @ _____

1-5 1/2" API insert @ 6 1999

1-5 1/2" Centralizer @ 1-6-99

CONSULTATION DIVISION
Wichita, Kansas

TOTAL _____

TAX _____

TOTAL CHARGE _____

DISCOUNT _____ IF PAID IN 30 DAYS

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

SIGNATURE [Signature]