

8-29

2-040640 202
R

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
200 Colorado Derby Building
Wichita, Kansas 67202

API NUMBER: 15-077-15287-0000

C NW NW, SECTION 19 TOWNSHIP 30 RANGE 6W

OPERATOR LICENSE # 6581 4620 FEET FROM S SECTION LINE
4620 FEET FROM E SECTION LINE

OPERATOR Bison Energy
NAME & 9320 East Central
ADDRESS Wichita, KS 67206

LEASE NAME: Hostetler #1
COUNTY: Harper
WELL TOTAL DEPTH: 4695'

152.58

CONDUCTOR PIPE: " @ ' "

SURFACE CASING: 8-5/8" @ 246'

ABANDONED OIL WELL GAS WELL _____ INPUT WELL _____ SMD _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: Shawnee Well Service
ADDRESS: Attica, KS LICENSE: _____

COMPANY TO PLUG AT: HOUR: _____ DAY: _____ MONTH: _____ YR: 1991

PLUGGING PROPOSAL RECEIVED FROM: Marvin Capps
COMPANY NAME: Shawnee Well Service PHONE: _____

WERE: 5-1/2" @ 4695'/150 sx - set CIBP @ 4600' - 35 sx @ 1150' - 35 sx @ 750' - circ 300' - perf 4660'-4664'.

PLUGGING PROPOSAL RECEIVED BY: Steve Van Gieson

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART (_____) NONE (_____)

COMPLETED: HOUR: 19:00 DAY: 29 MONTH: 8 YEAR: 1991

ACTUAL PLUGGING REPORT:
A CIBP was set @ 4600' & capped with 2 sx cmt - 5-1/2" was shot loose @ 3527' and pulled to 1173' - 35 sx cmt - 5-1/2" pulled to 760' & 35 sx cmt - 5-1/2" pulled to 300' & cmt circ to surf - remaining pipe pulled & cmt topped off.

REMARKS: B. J. Services #648740 40/60 2% gel

I DID OBSERVE THIS PLUGGING.

INVOICED

DATE 11-8-91

ENV. NO. 33641

8-29

Steve Van Gieson
Steve Van Gieson (AGENT)

FORM CP-2/3
REV. 3/90

ow