

1-14

2- 040920

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

API No. 15-077-10046 0000

API NUMBER: 4-3-58

NE/NE/NE SECTION 26 TOWNSHIP 31 RANGE 6W

OPERATOR LICENSE # 5259
OPERATOR Mia Oil Operation
NAME P O Box 33
ADDRESS Russell KS.

4950 FEET FROM S SECTION LINE
330 FEET FROM E SECTION LINE

LEASE NAME: Runnymede 2-2 (ORIG. CALLED LITSBY UT #2)
COUNTY: Harper (AND THEN HUDSON #3)
WELL TOTAL DEPTH: 4660 151.45
PIPE: 7" 4660 PBTD 4197
SURFACE CASIN 10 3/4 521'

ABANDONED OIL WELL _____ GAS WELL _____ INPUT WELL XX SWD _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: Quality Well Service
ADDRESS: Sterling KS. LICENSE: 31925

COMPANY TO PLUG AT: HOUR: _____ DAY: _____ MONTH: _____ YR: _____

PLUGGING PROPOSAL RECEIVED FROM: Richard McIntyre
COMPANY NAME: Quality Well Service PHONE: _____
WERE: _____

Sand to 3880 & 7 Sks.
50 sks. @ 1050
50 sks. @ 600'
Circ. From 200'-0'

RECEIVED
KANSAS CORPORATION COMMISSION
MAR 24 1998
3-24-98
CONSERVATION DIVISION
WICHITA, KS

PLUGGING PROPOSAL RECEIVED BY: Steve Van Gieson


PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART (X) NONE ()

COMPLETED: HOUR: 1200 DAY: 14 MONTH: 1 YEAR: 1998

ACTUAL PLUGGING REPORT: The Perfs. Were covered with sand from 4197-3310' and capped with 7 sks. Cement. The 7" was recovered from 2630' and pulled to 1050' where 50 sks. Of cement was spotted. The pipe was pulled to 600' where 50 sks. Of cement was spotted. The pipe was pulled to 200' where cement was circulated to surface.

REMARKS: Allied Cement Co. 60/40 Poz 4% gel

I DID OBSERVE THIS PLUGGING.


Steve VanGieson

FORM CP-2/3
REV. 3/90

INVOICED

DATE 3-25-98
INV. NO. 50304