

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-077-10046-00-00
Spot: NENENE Sec/Twnshp/Rge: 26-31S-6W
4950 feet from S Section Line, 330 feet from E Section Line
Lease/Unit Name: RUNNYMEDE Well Number: 2-2
County: HARPER Total Vertical Depth: 4660 feet

Operator License No.: 5259
Op Name: MAI OIL OPERATIONS, INC.
Address: 4514 COLE AVE., STE 804, LB 30
DALLAS, TX 75205

Conductor Pipe: Size feet:
Surface Casing: Size feet: 521
Production: Size feet:
Liner: Size feet:

11/14/98

Well Type: SWD UIC Docket No.: D25878.0 Date/Time to Plug: 01/14/1998 3:00 PM

Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.

Proposal Rcvd. from: RICHARD MCINTRYE Company: QUALITY WELL SERVICE Phone:

Proposed
Plugging
Method:

Sand to 3300' and 7sxs of cement. Rec. pipe 50sxs@1050'. 50sxs@550'. Circulate cement 200'-0'.

Plugging Proposal Received By: STEVE VANGIESON

Witness Type: Plugging Operations Partially Witnessed

Date/Time Plugging Completed: 01/14/1998 3:00 PM

KCC Agent: STEVE VANGIESON

Actual Plugging Report:

The perms. Were cover w/sand to 3301' and capped w/7sxs of cement. The casing was recovered from 2630', and pulled to 1050', where 50sxs of cement was spotted. The casing was pulled to 550' where 50sxs of cement was spotted. The casing was pulled to 200', where cement was circulated to surface.

RECEIVED
KCC DISTRICT #2

DEC 15 2000


12-15-00
WICHITA, KS

Remarks: ALLIED CEMENTING 60/40 POZ 4% GEL.

Plugged through: CSG

District: 02

Signed



(TECHNICIAN)