

2 060015

1-18

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 077-21,145 - 0000

C SE SW, SEC. 28, T 31 S, R 5W W/E

660 feet from S section line

3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5898

Lease Name Gerber Well # 1

Operator: Voth Oil Company, Inc.

County Harper 151.19

Name & Address 6235 W. Kellogg

Well Total Depth 4652 feet

Wichita, KS 67209

Conductor Pipe: Size _____ feet

Surface Casing: Size 8-5/8 feet 264

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated 5-1/2" @ 4649' w/200 sx

Plugging Contractor Great Bend Casing License Number 4635

Address P.O. Box 768, Great Bend, KS 67530

Company to plug at: Hour: 8:30 Day: 18 Month: 1 Year: 19 90

Plugging proposal received from Gary Burke

(company name) Great Bend Casing (phone) 316-793-9711

were: Sand back 50' & 5 sx cap - shoot casing & pull to 1300' 25 sx - pull casing to 600' 25 sx - pull casing to 300' - circ cmt to surface.

Plugging Proposal Received by Steve Van Gieson (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 10:30 Day: 18 Month: 1 Year: 1990

ACTUAL PLUGGING REPORT Sand back to 4602' - cap with 5 sx cmt - shoot and pull casing to 1300' - pump 25 sx cmt thru 5-1/2" - pull casing to 580' - pump 25 sx cmt thru 5-1/2" - pull casing to 300' & circ 188 sx cmt thru 5-1/2" to surface - pulled remaining 5-1/2" - recheck of well showed cmt dropped 120', 60' water - ran tubing to 120' & circ 40 sx common to surface.

Remarks: United #791 60/40 4% - recovered 3237' of 5-1/2" (If additional description is necessary, use BACK of this form.)

5 1990
2-5-90
Conservation Div. 207
Wichita, Kansas

INVOICED

(do not check) observe this plugging.

DATE 2-16-90

Signed *David White* (TECHNICIAN)

INV. NO. 27505

1-18