

2 040531

1-26

207 R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 077-01,005 ~~0001~~ D-25,116

SW SW SE, SEC. 28, T 31 S, R 5W WE

330 feet from S section line

2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5898

Lease Name Heibert Well # 1

Operator: Voth Oil Company

County Harper 157.43

Name & Address 6235 West Kellogg

Well Total Depth 4844 feet

Wichita, KS 67209

Conductor Pipe: Size _____ feet

Surface Casing: Size 8-5/8 feet 351

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SHD Well X D&A _____
D-25,116

Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pulling License Number 4635

Address Great Bend, KS

Company to plug at: Hour: _____ Day: _____ Month: _____ Year: 19 _____

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pulling (phone) _____

were: 4-1/2" 4843' - OH 4843-4844' - sand & 4 sx to 4790' - 25 sx @ 600' -

25 sx at 1300' - circ from 400' to 0

Plugging Proposal Received by Steve Van Gieson
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part X None _____

Operations Completed: Hour: 15:30 Day: 26 Month: 1 Year: 19 90

ACTUAL PLUGGING REPORT OH was sanded back to 4790' and capped with 4 sx
cmt - 4-1/2" casing was shot off and pulled to 1307' where 25 sx cmt was
spotted - casing was pulled to 598' and another 25 sx was spotted - casing
was pulled to 396' and cmt was circ to surface.

Remarks: United #877 60/40 4% gel

(If additional description is necessary, use BACK of this form.)

(Did XXXXXXXXXX observe this plugging.)

INVOICED

DATE 4-12-90

INV. NO. 27833

Signed [Signature]
(TECHNICIAN)

APR 04 1990
4-4-90
CONSERVATION DIVISION
Wichita, Kansas