

10-12

2-040749

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
200 Colorado Derby Building  
Wichita, Kansas 67202

API NUMBER: 15-077-21,154 <sup>21249-0000</sup>

NE NE, SECTION 10 TOWNSHIP 31 RANGE 8W

OPERATOR LICENSE # 6581 4950 FEET FROM S SECTION LINE  
1300 FEET FROM E SECTION LINE

OPERATOR Bison Energy Corp.  
NAME & 9320 E. Central  
ADDRESS Wichita, KS 67206

LEASE NAME: Muir #2A-10  
COUNTY: Harper  
WELL TOTAL DEPTH: 4443' 144.40

CONDUCTOR PIPE: \_\_\_\_\_

SURFACE CASING: 8-5/8" @ 221'

ABANDONED OIL WELL \_\_\_\_\_ GAS WELL \_\_\_\_\_ INPUT WELL \_\_\_\_\_ SMD \_\_\_\_\_ D&A X

OTHER WELL AS HEREINAFTER INDICATED: \_\_\_\_\_

PLUGGING CONTRACTOR: Shawnee Well Service  
ADDRESS: Attica, KS LICENSE: \_\_\_\_\_

COMPANY TO PLUG AT: HOUR: \_\_\_\_\_ DAY: \_\_\_\_\_ MONTH: \_\_\_\_\_ YR: 1992

PLUGGING PROPOSAL RECEIVED FROM: C. J. Lett III  
COMPANY NAME: Bison Energy Corp. PHONE: \_\_\_\_\_

WERE: Perfs 4404-07' - 5-1/2" 4449' - CIBP 4000' & 2 sx -  
35 sx 1100' - 35 sx 700' - circ cmt 275'

PLUGGING PROPOSAL RECEIVED BY: \_\_\_\_\_

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL ( \_\_\_\_\_ ) PART ( \_\_\_\_\_ ) NONE ( X )

COMPLETED: HOUR: 1400 DAY: 12 MONTH: 10 YEAR: 1992

ACTUAL PLUGGING REPORT:  
A CIBP was set @ 4000' & capped w/2 sx cmt to cover  
perfs - 5-1/2" recovered frm 2695' & pulled to 1100'  
& 35 sx cmt spotted - 5-1/2" pulled to 700' & 35 sx cmt  
spotted - 5-1/2" pulled to 275' & cmt circ to surf  
remaining 5-1/2" pulled (2697') from wellbore & cmt  
topped off.

REMARKS: B. J. Services 60/40 4% gel

RECEIVED  
KANSAS CORPORATION COMMISSION

I DID NOT OBSERVE THIS PLUGGING.

INVOICED  
DATE 1-5-93  
INV. NO. 37103

/s/  
Steve Van Gieson  
(AGENT)

DEC 30 1992  
12-30-92  
CONSERVATION DIVISION  
WICHITA, KS  
FORM CP-2/3  
REV. 3/90