

10-18

2-040576

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
200 Colorado Derby Building
Wichita, Kansas 67202

API NUMBER: 15-077-21,217-0000

C SE SW, SECTION 10 TOWNSHIP 31 RANGE 8W

OPERATOR LICENSE # 6581 660 FEET FROM S SECTION LINE
3300 FEET FROM E SECTION LINE

OPERATOR Bison Energy Corp.
NAME & P. O. Box 782317
ADDRESS McPherson, KS 67278

LEASE NAME: Stephens #4-10
COUNTY: Harper

WELL TOTAL DEPTH: 4783' 155.44

CONDUCTOR PIPE: _____
SURFACE CASING: 8-5/8" @ 222'

ABANDONED OIL WELL _____ GAS WELL _____ INPUT WELL _____ SMD _____ D&A X
OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: Lobo Drilling
ADDRESS: Great Bend, KS LICENSE: _____

COMPANY TO PLUG AT: HOUR: _____ DAY: _____ MONTH: _____ YR: 1990

PLUGGING PROPOSAL RECEIVED FROM: Ervin Neibors
COMPANY NAME: Lobo Drilling PHONE: _____

WERE: 35 sx 1500' - 35 sx 950' - 35 sx 275' - 25 sx 60' - 10
sx R.H. - 10 sx M.H.

PLUGGING PROPOSAL RECEIVED BY: Steve Van Gieson

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (_____) PART (_____) NONE (X)

COMPLETED: HOUR: 12:00 DAY: 18 MONTH: 10 YEAR: 1990

ACTUAL PLUGGING REPORT:

The drill pipe was run open end to 1500' where 35 sx
cmt was spotted in place - drill pipe was pulled to
950' and 275' where 35 sx cmt spotted at both depths -
drill pipe pulled to 60' & hole circ w/25 sx cmt - rat
hole and mouse hole both circ w/10 sx cmt each.

REMARKS: _____

I DID NOT OBSERVE THIS PLUGGING.

INVOICED

DATE 11-9-90

INV. NO. 29918

Steve Van Gieson
Steve Van Gieson (AGENT)

RECEIVED
STATE CORPORATION COMMISSION

11-5-90
NOV 5 1990

CONSERVATION DIVISION
Wichita, Kansas

FORM CP-2/3
REV. 3/90