

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-077-20622-00-00
Spot: CNWSW Sec/Twnshp/Rge: 10-31S-8W
1980 feet from S Section Line, 4620 feet from E Section Line
Lease/Unit Name: STEPHENS Well Number: 3
County: HARPER Total Vertical Depth: 4499 feet

Operator License No.: 5003
Op Name: MCCOY PETROLEUM CORPORATION
Address: 453 S. WEBB RD. STE 310 PO BOX 78020
WICHITA, KS 67278

Conductor Pipe: Size feet: 8 1/4 146-22
Surface Casing: Size 8.625 feet: 265 200 SX CMT
Production: Size 5.5 feet: 4495 100 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 07/19/2002 12:40 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: JOE MAES Company: QUALITY WELL SERVICE Phone:

Proposed Plugging Method: Perfs 4376'-82'. Sand to 4325' and 5sxs. 35sxs-1350', 35sxs-900' and circulate to 315'.

Plugging Proposal Received By: STEVE VANGIESON WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 07/19/2002 12:40 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

The perfs were covered w/sand from 4484'-4325' and capped w/5sxs of cement. The casing was recovered from 2105' and pulled to 1350' where 35sxs of cement was spotted. The casing was pulled to 900' where 35sxs of cement was spotted. The casing was pulled to 315' where cement was circulated to surface. The remaining casing was pulled and topped off.

RECEIVED
KCC DISTRICT #2


JUL 24 2002
7-24-02
WICHITA, KS

Remarks: ACID SERVICE 60/40 4% GEL

Plugged through: CSG

District: 02

Signed



(TECHNICIAN)

INVOICED

DATE 7-25-02

WV. NO. 2003060090