

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

2-19

2-040871

K5077-00028-00-02

API NUMBER: 1/6/67

SW SW NE, SECTION 10 TOWNSHIP 31 RANGE 8W

OPERATOR LICENSE # 31532 2970 FEET FROM S SECTION LINE
OPERATOR BISON PRODUCTION COMPANY 2310 FEET FROM E SECTION LINE
NAME & 9320 EAST CENTRAL
ADDRESS WICHITA, KS 67206
LEASE NAME: MUIR A-1
COUNTY: HARPER 169.19
WELL TOTAL DEPTH: 5206'
PIPE:
SURFACE CASING: 8 5/8" @ 154'

ABANDONED OIL WELL GAS WELL INPUT WELL SWD D&A

OTHER WELL AS HEREINAFTER INDICATED:

PLUGGING CONTRACTOR: SHAWNEE WELL SERVICE

ADDRESS: ATTICA, KS LICENSE: 30346

COMPANY TO PLUG AT: HOUR: DAY: MONTH: YR: 1997

PLUGGING PROPOSAL RECEIVED FROM: RUSSEL MEYERS

COMPANY NAME: BISON PRODUCTION COMPANY PHONE: (316) 636-1801

WERE: 5 1/2" AT 4952'

PERFS 4402-4405'

PBTD 4952'

PLUGGING PROPOSAL RECEIVED BY: MIKE WILSON

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE ()

COMPLETED: HOUR: 12:00 DAY: 19 MONTH: 2 YEAR: 1997

ACTUAL PLUGGING REPORT: THE PERFS WERE COVERED WITH SAND FROM 4952' TO 4330' AND CAPPED WITH 5 SACKS OF CEMENT. THE 5 1/2" WAS RECOVERED FROM 1505' AND PULLED TO 1420' WHERE 35 SACKS OF CEMENT WAS SPOTTED. THE 5 1/2" WAS PULLED TO 892' WHERE 35 SACKS OF CEMENT WAS SPOTTED. THE 5 1/2" WAS PULLED TO 251' WHERE CEMENT WAS CIRCULATED TO SURFACE. REMAINING PIPE WAS PULLED AND CEMENT TOPPED OFF.

REMARKS: 60/40 POZ 4% GEL ALLIED CEMENT

RECEIVED
KANSAS CORPORATION COMMISSION
FEB 28 1997
2-28-97
CONSERVATION DIVISION
WICHITA, KS

INVOICED

DATE MAR 03 1997

INTL 47682

2-19

I DID OBSERVE THIS PLUGGING.

STEVE VAN GIBSON