

API NUMBER: 15-077-20947-0000

NW SE SE, SECTION 20 TOWNSHIP 31 RANGE 8W

OPERATOR LICENSE # 5003

990 FEET FROM S SECTION LINE

990 FEET FROM E SECTION LINE

OPERATOR McCoy Petro Corp.

NAME & 110 S. Main #500

ADDRESS Wichita Ks 67212

LEASE NAME: Burgess Well#B-3

COUNTY: Harper

WELL TOTAL DEPTH: 4403 143.09

CONDUCTOR PIPE: _____

SURFACE CASING: 8-5/8 @ 254

ABANDONED OIL WELL GAS WELL _____ INPUT WELL _____ SLD _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: Clarke Corp.

ADDRESS: Medicine Lodge Ks LICENSE: _____

COMPANY TO PLUG AT: HOUR: _____ DAY: _____ MONTH: _____ YR: 1993

PLUGGING PROPOSAL RECEIVED FROM: Daryl Hanson

COMPANY NAME: McCoy Petro Corp. PHONE: _____

WERE: OH 4393-4403 Sand Back to 4340 & 5sx
5-1/2 4393' 30sx 1350', 30sx 900', circ 310
TOC 3700

PLUGGING PROPOSAL RECEIVED BY: SVG

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE ()

COMPLETED: HOUR: 1700 DAY: 9 MONTH: 4 YEAR: 1993

ACTUAL PLUGGING REPORT:

The open hole was sanded back to 4340' & capped with 5sx of cmt. The 5-1/2" was recovered from 3350' & pulled from the wellbore. Tubing was back in Wellbore to 1543 where 30sx of cmt was spotted. The tubing was pulled to 906' where 30sx of cmt was spotted. The tubing was pulled to 312' where cmt was circ to surface.

RECEIVED
KANSAS CORPORATION COMMISSION

REMARKS: Allied 60/40 4% gel
I DID OBSERVE THIS PLUGGING.

MAY 27 1993

5-27-93

CONSERVATION DIVISION
WICHITA, KS

Steve Van Gieson

Steve Van Gieson

(AGENT)

FORM CP-2/3
REV. 3/90

INVOICED

DATE 5-28-93

INV. NO. 37781

dw