

2 040234

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 07720099-0000 Old Well.

TECHNICIAN'S PLUGGING REPORT

Operator License # 5238

Operator: Petroleum Incorporated.  
Name & Address: 300 W Douglas Ste 800  
R.H. Bervey Bldg  
Wichita Ks 67202

SEC. 20, T. 31 S. R. 8  
3300 feet from section line  
3300 feet from section line

Lease Name Washbon Well # 1

County Harper

Well Total Depth 4390 142.68 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 217

Abandoned Oil Well  Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Rockhole Engineers License Number 5111

Address Great Bend Ks

Company to plug at: Hour: \_\_\_\_\_ Day: \_\_\_\_\_ Month: \_\_\_\_\_ Year: 19 \_\_\_\_\_

Plugging proposal received from D. P. Pulley

(company name) Rockhole Engineers. (phone) \_\_\_\_\_

were: Sand to 4320 and 5sks - 3H 15 gel 100 sk

5 1/2 4389

Perf 4373-83

Plugging Proposal Received by Sto Linder  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part  None \_\_\_\_\_

Operations Completed: Hour: 1100 Day: 19 Month: 12 Year: 19 85

ACTUAL PLUGGING REPORT The 5 1/2" casing was sandbed back to 4320' and 5 sacks was used to cap the sand, to cover off the perforations. The 5 1/2" was shot and recovered at 3000'. The Top was squeeze plugged thru the 8 5/8" by pump 3 sacks of hulls, 15 sacks of gel and 50 sacks of cement, a wyein plug and the another 50 sacks of cement

Remarks: ST 200# MX 400# Allied Cementing 2095  
(If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

Signed Sto Linder  
(TECHNICIAN)

DATE JAN 02 1986

NOV. NO. 11805 12-19

1-2-86