

To: 1 052040
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202
TECHNICIAN'S PLUGGING REPORT

API NUMBER 15- 165-21,699-0000
App. C SE, SEC. 18, T 18 S, R 17 W/E
1430 feet from S section line
1320 feet from E section line

Operator License # 6875
Operator: Marmik Oil Company
Name & Address: 200 N. Jefferson, Ste. 500
El Dorado, AR 71730

Lease Name Besperat Well # 1
County Rush
Well Total Depth 3903 126.84 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1158

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ O&A X
Other well as hereinafter indicated _____

Plugging Contractor Duke Drilling Co. License Number 5929
Address 310 W. Central, Wichita, KS 67202

Company to plug at: Hour: _____ Day: 11 Month: 5 Year: 19 96

Plugging proposal received from Rich Wheeler
(company name) Duke Drilling Co. (phone) 316-267-1331

purpose: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1148-74'
1st plug at Arbuckle with 50 sx cement, 2nd plug at 1190' with 50 sx cement,
3rd plug at 500' with 40 sx cement, 4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X
Operations Completed: Hour: 11:30 p. Day: 11 Month: 5 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug at 1190' with 50 sx cement,
2nd plug at 500' with 40 sx cement,
3rd plug at 40' with 10 sx cement,
4th plug to circulate rathole with 15 sx cement.

RECEIVED
KANSAS CORPORATION COMMISSION
5-21-96
MAY 21 1996

CONSERVATION DIVISION
WICHITA, KS

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED
I hereby certify that I have observed this plugging.

DATE 5-23-96
INV. NO. 45634

Signed Richard M. Lacey (TECHNICIAN)

EFFECTIVE DATE: 4-28-96
DISTRICT # 1
SEAT Yes No

State of Kansas
NOTICE OF INTENTION TO DRILL 165-21,699-0000

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date 5 1 1996
month day year

Spot
Approx. G. SE. Sec 18. Twp 18. S. Rg 17. X

OPERATOR: License # 6875
Name: Marmik Oil Company
Address: 200 N. Jefferson, Suite 500
City/State/Zip: El Dorado, AR 71730
Contact Person: Curtis G. Morrill
Phone: 501-862-8546

1430 feet from South/ North line of Section
1320 feet from East/ West line of Section
IS SECTION X REGULAR IRREGULAR?

(NOTE: Locate well on the Section Plat on Reverse Side
County: Rush
Lease Name: Besperat Well #: 1
Field Name:

CONTRACTOR: License #: 5929
Name: Duke Drilling

Is this a Prorated/Spaced Field? yes X no
Target Formation(s): Arbuckle
Nearest Lease or unit boundary: 1320'
Ground Surface Elevation: 2008 feet MSL
Water well within one-quarter mile: X yes
Public water supply well within one mile: X yes
Depth to bottom of fresh water: 180'
Depth to bottom of usable water: 260'
Surface Pipe by Alternate: X 1 2
Length of Surface Pipe Planned to be set: 280'
Length of Conductor pipe required: none

Well Drilled For: Well Class: Type Equipment:
X Oil ... Enh Rec ... Infield X Mud Rotary
... Gas ... Storage ... Pool Ext. ... Air Rotary
... OWWO ... Disposal X Wildcat ... Cable
... Seismic: ... # of Holes ... Other

If OWWO: old well information as follows:
Operator:
Well Name:
Comp. Date: Old Total Depth

Projected Total Depth: 4000'
Formation at Total Depth: Arbuckle
Water Source for Drilling Operations:
... well ... farm pond ... other

Directional, Deviated or Horizontal wellbore? yes X no
If yes, true vertical depth:
Bottom Hole Location:
Exp. 10/23/96

Will Cores Be Taken? yes no
If yes, proposed zone:
280' Alt. I Req.

MAY 2 1996
5-21-96
CONSERVATION DIVISION

AFFIDAVIT

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101. et. seq.

Pusher: Rich
SPUD DATE: 5-6-96 INIT. Spud
LENGTH SURFACE PLANNED: 1150 I
RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.
RATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPE 8 3/8 @ 1158 CONDUCTOR
ANHYDRITE T- 1144 B- 1174 ELEVATION
TD 3203 FORMATION
RAR PIPE @ DV TOOL ALT II DONE
SX Y N
Arbuckle Plug @ 507 Ft. W/ 57 SX
Ingr./Council @ Ft. W/ SX
Anhydrite Base @ 1190 Ft. W/ 50 SX
1/2 Base Anyh. @ 500 Ft. W/ 40 SX
1/2, 1/2 Plug @ Ft. W/ SX
Bottom Surface @ Ft. W/ SX
40' Plug @ 40 Ft. W/ 10 SX
RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ SX
WATER WELL SX (Irr. Well Pond Hauling X)
TECHNICIAN R. L. DATE 5-10-96
TYPE OF CEMENT 60/40 per 6' pipe
STARTING TIME 11:30 AM DATE 5-11-96
COMPLETION TIME 11:30 AM DATE 5-11-96
CEMENT COMPANY Allect