

1 050551

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-165-21,288-0000 *R*

NW SE NW, SEC. 33, T 18 S, R 17 W/E
3630 feet from S section line
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5131

Lease Name Serpan Well # 1

Operator: Thunderbird Drilling, Inc.

County Rush 124.32

Name & Address P. O. Box 18407

Well Total Depth 3825 feet (Arbuckle)

Wichita, KS 67218

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1130

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor Thunderbird Drilling, Inc. License Number 5131

Address P. O. Box 18407, Wichita, KS 67218

Company to plug at: Hour: 9:00 pm Day: 8 Month: June Year: 1985

Plugging proposal received from Ed Cook

(company name) Thunderbird (phone) 316-685-1441

Elevation 2008

work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1116-1146

1st plug at 3600' with 50 sx cement

2nd plug at 1170' with 40 sx cement

3rd plug at 570' with 40 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 11:00 pm Day: 8 Month: June Year: 1985

ACTUAL PLUGGING REPORT 1st plug at 3600' with 50 sx cement, 2nd plug at 1170' with 40

sx cement, 3rd plug at 570' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls -

plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with

15 sx cement.

JUN 17 1985
6-17-85
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED
(You should not) observe this plugging.

DATE 6-20-85

Signed Richard W. Lacey
(TECHNICIAN)

INV NO. 8648
6-8 JUL 12 1985