

To: 1 052084
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 165-21,607-0000
NE SW NW, SEC. 31, T 18 S, R 17 W/EX
3630 feet from S section line
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5393
Operator: A.L. Abercrombie, Inc.
Name:
Address Rt. 1, Box 56
Great Bend, KS 67530

Lease Name Pohoralek Well # 1
County Rush 122.42
Well Total Depth 3767 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 1128

Abandoned Oil Well Gas Well Input Well SWD Well O&A
Other well as hereinafter indicated

Plugging Contractor Allied Cementing License Number
Address

Company to plug at: Hour: 9:30 a.m. Day: 14 Month: 11 Year: 19 96

Plugging proposal received from Darrell Dipman
(company name) Abercrombie (phone) 316-793-8186

Work: 5 1/2" at 3765' w/125 sx cement, Open hole 3765-67'
1st plug pump 2 sx hulls with 40 sx cement to 3750',
2nd plug at 1170' with 50 sx cement,
3rd plug at 620' with 40 sx cement,
4th plug at 40' with 10 sx cement.

Plugging Proposal Received by Gary Winters
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11:50 a.m. Day: 14 Month: 11 Year: 19 96

ACTUAL PLUGGING REPORT 5 1/2" X 8 5/8" pressured to 700 psi.
Pumped down 5 1/2" with 300 lbs. hulls, 25 sx cement, 4 sx gel, and 105 sx cement.
Maximum pressure 2700 psi and shut in 50 psi.

11-19-96

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery.
(If additional description is necessary, use BACK of this form.)

INVOICED
DATE NOV 21 1996
INV. NO. 47004

to observe this plugging.

Signed Richard W. Lacey
(TECHNICIAN)