

1080201

TO:

API NUMBER 15-165-20,689-0001

5-29

STATE CORPORATION COMMISSION

25'E-N/2-SW SEC. 2, T 18 S, R 17 W

CONSERVATION DIVISION - PLUGGING SECTION 1980 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 3935 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME OBORNY WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY RUSH

OPERATOR LICENSE # 30717

WELL TOTAL DEPTH 3589 116,65 FEET

OPERATOR: DOWNING-NELSON OIL CO., INC.

PRODUCTION CSG: SIZE 4-1/2" FEET 3574' W/ 75 SX

NAME AND P.O. BOX 372

SURFACE CSG 8-5/8" FEET 1071'

ADDRESS HAYS KS 67601

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR PARAMOUNT ENTERPRISES, INC. LICENSE NUMBER 3763

ADDRESS 2905 BARCLAY DRIVE HAYS KS 67601

COMPANY TO PLUG AT: HOUR: 8:00 DAY: 29 MONTH: 5 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM RON GEIST

(COMPANY NAME) PARAMOUNT ENTERPRISES, INC. (PHONE) 785-628-1099

WERE: PUMP 100# COTTONSEED HULLS 25sx CEMENT DISPLACE TO 3200' SHOOT CASING, 2nd PLUG @

1090'W/50sx ,3rd PLUG @ 450' SPOT 40 SX PLUG ,4th PLUG @ 40'W/10SX CEMENT

PLUGGING PROPSAL RECEIVED BY: RICHARD LACY

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE

OPERATIONS COMPLETED: HOUR: 1:00PM DAY: 29 MONTH: 5 YEAR: 1998

ACTUAL PLUGGING REPORT OPEN HOLE FROM 3574'-79', PERFS @3554'-56', 1st PLUG PUMPED 100#

COTTONSEED HULLS W/25sx CEMENT DISPLACED TO 3200'MAX PSI 1000# SHUT IN @ 500# LOG TECH SHOT
4 1/2 CASING @ 2980', 2nd PLUG @ 1090'W/50sx CEMENT ,3rd PLUG @ 450'W/50SX CEMENT ,4th PLUG
@40'W/10sx CURCULATED TO SURFACE

KANSAS CORPORATION COMMISSION

JUN 03 1998
6-3-98

CONSERVATION DIVISION
WICHITA, KS

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2980' 4 1/2 CASING
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

SIGNED *Kevin D. Shurtz*
(TECHNICIAN) FORM CP-2/3

INVOICED

DATE 6-8-98

INV. NO. 5-0681

5-29 SEP 18 1998