

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

#			

Locate well correctly on above
Section Plat

Rush County. Sec. 8 Twp. 18 Rge. 16 (E) W (W)
 Location as "NE/CNW&SW" or footage from lines NE NE NW
 Lease Owner Solar Oil Co.
 Lease Name Betta Well No. 1
 Office Address 1117 Un. Natl. Bldg. Wichita
 Character of Well (completed as Oil, Gas or Dry Hole) Gas
 Date well completed Dec. 12, 1957
 Application for plugging filed Aug. 1, 1963
 Application for plugging approved Aug. 6, 1963
 Plugging commenced Aug. 22, 1963
 Plugging completed Aug. 24, 1963
 Reason for abandonment of well or producing formation No longer a producer.

If a producing well is abandoned, date of last production July 10, 1963
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
 Producing formation Regan Depth to top 3535' Bottom 3537' Total Depth of Well 3560' Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	1056'	None
				5 1/2	3558'	3066'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged back with sand from 3560' to 3515'. Mixed and dumped 4 sq. cement from 3515' to 3483'. Pulled casing. Mudded hole to 470'. Set 20' rock bridge from 470' to 450'. Dumped 6 yds. of ready mixed cement from 450' to base of the cellat.

RECEIVED
STATE CORPORATION COMMISSION

SEP 9 1963
9-9-63

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Ace Pipe Pulling Co.
 Address Box 304 Great Bend, Ks.

STATE OF Kansas, COUNTY OF Barton, ss.
 William D. Hoherecht (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *William D. Hoherecht*

Box 304 Great Bend, Ks.

(Address)

SUBSCRIBED AND SWORN TO before me this 28 day of August, 1963

My commission expires: April 18, 1967
My commission expires _____

Glenn M. Irick
Glenn M. Irick Notary Public.

COMPANY:
 Solar Oil Company
 705 Union National Building
 Wichita, Kansas

Rotary Drilling Commenced: 11-30-57
 Rotary Drilling Completed: 12-14-57

LOCATION:
 Betz No. 1
 NE 1/4 Sec. 8-18S-16W
 Rush County, Kansas

CONTRACTOR:
 Shelley-Miller Drilling Company
 205 Miller Building
 Wichita, Kansas

CASING RECORD:
 5 5/8" 24# Smls Casing set @ 1056, cemented with 425 sacks cement.
 5 1/2" 17# Casing set @ 3528, cemented with 75 sacks cement.

LOG
 (Measurements from top of Rotary Bushing to bottom of formation)

Clay	70
Sand	74
Shale and Shells	460
Sand	570
Shale and Shells	765
Red Bed	1,047
Anhydrite	1,038
Shale and Shells	1,775
Lime and Shale	3,070
Lime	3,225
Lime and Shale	3,260
Lime	3,520
Sand	3,540
Sand - Core	3,545
Sand	3,560 Rotary T.D.

RECEIVED
 STATE CORPORATION COMMISSION
 JUL 23 1963
 7-23-63
 CONSERVATION DIVISION
 Wichita, Kansas

The undersigned, Richard A. Shelley, Partner of Shelley-Miller Drilling Company, hereby certifies in behalf of said company, that the above log is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

SHELLEY-MILLER DRILLING COMPANY

By Richard A. Shelley

STATE OF KANSAS)
 COUNTY OF HEDGWICK) SS

BE IT REMEMBERED, that on this 19th day of December, 1957, before me, the undersigned, a Notary Public, duly commissioned in and for the county and state aforesaid, came Richard A. Shelley, Partner, and known to me to be the same person who executed the foregoing instrument of writing in behalf of Shelley-Miller Drilling Company, as a Partner of said company, and he duly acknowledged the execution of the same for himself and for said company.

IN WITNESS WHEREOF I have hereunto set my hand and official seal on the day and year last above written.

Louisa M. Lawrence
 Notary Public

My Commission Expires:
 March 24, 1960