

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
P. O. Box 17027  
Wichita, Kansas 67217  
NORTH

## WELL PLUGGING RECORD


Locate well correctly on above  
Section Plat

Rush County, Sec. 22 Twp. 17S Rge. (E) 19 (W)  
Location as "NE/CNW/SW" or footage from lines C NE NW  
Lease Owner Pickrell Drilling Company  
Lease Name Rife "E" Well No. 1  
Office Address 705 Fourth National Bank Bldg., Wichita, Kansas 67202  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed June 17 19 72  
Application for plugging filed June 17 19 72  
Application for plugging approved June 17 19 72  
Plugging commenced June 17 19 72  
Plugging completed June 17 19 72  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo F. Massey  
Producing formation Depth to top Bottom Total Depth of Well 4015 Feet  
Show depth and thickness of all water, oil and gas formations.

## OIL, GAS OR WATER RECORDS

## CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	258'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Bottom Plug @ 550' w/70 sacks, Middle Plug @ 240' w/20 sacks,  
Top Plug @ 140' w/10 sacks.


RECEIVED  
STATE CORPORATION COMMISSION  
JUN 27 1972  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Pickrell Drilling Company  
Address 705 Fourth National Bank Building, Wichita, Kansas 67202

STATE OF Kansas, COUNTY OF Sedgwick ss.  
C. W. Sebitts

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. W. Sebitts  
705 Fourth National Bank Bldg., Wichita, Kansas  
(Address)



SUBSCRIBED AND SWORN to before me this 21st day of June, 1972  
January 19, 1973

Esther Lamone  
Notary Public.

15-165-26436-0000  
ROTARY DRILLING LOG

COMPANY: Pickrell Drilling Company  
705 Fourth National Bank Bldg.  
Wichita, Kansas 67202

Rotary Drilling Commenced 6/9/72

Rotary Drilling Completed 6/17/72

LOCATION: Rife "E" No. 1, C NE NW Section 22-17S-19W  
Rush County, Kansas

CONTRACTOR: **PICKRELL DRILLING COMPANY**  
Wichita, Kansas

CASING RECORD: Run 6 Jts. 8-5/8" surface casing set @ 258' KB. Cemented  
w/258 sacks. Completed 6:30 P.M. Circulated.

D & A, No oil string run. Plugged down 8:15 A.M. June 17, 1972.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

		<u>C.F.S.</u>
40	Surface Soil - Shale	
260	Shale - Sand Streaks	3595
435	Shale	3625
480	Sand	3685
845	Shale & Red Bed	3697
1050	Sand	3780
1405	Red Beds - Shale	3960
1441	Anhydrite	3973
1565	Red Beds - Shale	3987
2005	Shale	4015
2275	Shale & Lime	
3410	Lime	
3545	Shale & Lime	
3835	Lime	
3973	Lime - Chert	
4015	Cherty Lime & Arb, RTD	

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 27 1972  
CONSERVATION DIVISION  
Wichita, Kansas

Slope Tests  
2000  
2500  
3000  
3500  
4000

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY

By C. W. Sebitts Attorney-in-Fact

STATE OF KANSAS }  
COUNTY OF SEDGWICK } ss.:

On this 21st day of June, 19 72, before me the undersigned, a Notary Public, in and for

C. W. Sebitts

the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact, and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: January 19, 1973

Esther Lamone  
Notary Public