

15-1165-21883-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Rush SEC. 17 TWP. 17 RGE. 19 E/W
Location as in quarters or footage from lines:
NE NE SE

Locate Well
correctly on above
Section Platt.

Lease Owner Crude Producers Inc.
Lease Name Bex Well No. #1
Office Address Box 55 Russell, Kansas 67665
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
Date Well Completed 5-7-83
Application for plugging filed 5-7-83
Plugging commenced 5:00 am 5-7-83
Plugging completed 9:30 am 5-7-83
Reason for abandonment of well or producing formation Dry Hole

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Steve Durrant
Producing formation Depth to top bottom T.D. 3960'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole to 1350' with heavy mud and mixed 50 sacks of cement and pumped in hole thru drill pipe.

Filled hole to 780' with heavy mud and mixed 50 sacks of cement and pumped in hole thru drill pipe.

Filled hole to 300' with heavy mud and mixed 40 sacks of cement and pumped in hole thru drill pipe.

Filled hole to 40' built a solid bridge pushed down plug and mixed 10 sacks of cement and filled hole to bottom of cellar; mixed 10 sacks and poured into the rat hole.


All cement used was 60-40 Poz Mix 2 % Gel 3% CC

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Revin Drlg., Inc.

STATE OF Kansas COUNTY OF Russell, ss.

Stanley C. Lingreen (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.



(Signature) Stanley C. Lingreen

Box 293 Russell, Kansas 67665
(Address)

SUBSCRIBED AND SWORN TO before me this 10th day of May, 19 83

My Commission expires: November 10, 1984

Paula J. Gibson
Notary Public.

RECEIVED
STATE CORPORATION COMMISSION

5-13-83
MAY 13 1983

CONSERVATION DIVISION
Wichita, Kansas