

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-077-20099

LEASE NAME Washbon

WELL NUMBER # 1

SPOT LOCATION C SW NW

SEC. 20 TWP. 31 RGE. 8 (E) or (W) (W)

COUNTY Harper

Date Well Completed _____

Plugging Commenced 12-12-85

Plugging Completed 12-19-85

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Petroleum Inc.

ADDRESS Box 1447, Great Bend, Ks. 67530

PHONE # (316)-793-8968 OPERATORS LICENSE NO. 5238

Character of Well oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Two (2)

Is ACO-1 filed? _____ If not, is well log attached? With application

Producing formation _____ Depth to top _____ bottom _____ T.D. 4390'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	217'	None
				5-1/2"	4389'	2,973.40'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from _____ feet to _____ feet each set.

Dumped snad to 4,320' and 5 sacks cement. Shot casing at 3900', 3500' and 3000' Pulled 97 joints of 5-1/2" casing. Squeezed well with 15 sacks gel, 3 sacks hulls, 50 sacks cement, released plug and pumped 50 sacks 60/40 pozmix cement with 3% added gel and 2% calcium chloride. Maximum pressure was 400 psi and shutin 200 psi.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Gt. Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold
(Address) James W. Rockhold
Box 698, Gt. Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 27th day of December, 1985

STATE NOTARY PUBLIC
KANSAS
IONA M. LEATHERMAN
Barton County, Kansas
My Appt. Exp. 9-26-87

STATE NOTARY PUBLIC
Iona M. Leatherman
Notary Public

My Commission expires: _____

DEC 30 1985
12-30-85

CONSERVATION DIVISION
Wichita, Kansas