

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-077-20947-00-00

API NUMBER 15-077-20,447-0000

LEASE NAME Burgess

WELL NUMBER B-3

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 20 TWP. 31S RGE. 8 ~~W~~ (W)

COUNTY Harper

Date Well Completed N/A

Plugging Commenced 4-6-93

Plugging Completed 4-9-93

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR McCoy Petroleum Corporation

ADDRESS 110 S. Main, Suite 500, Wichita, KS 67202

PHONE# (316) 265-9697 OPERATORS LICENSE NO. 5003

Character of Well Good

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 4-5-93 (date)

by Steve Vangison (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached?

Producing Formation Depth to Top Bottom T.D.

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	254	
				5 1/2	4393	3350

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each section.
Bottom plug, sanded to 4340 put 5sx cement with dump bailer at 4340, cut and pulled casing ran tubing to 1343 spotted 30sx cement, pulled tubing to 907 spotted 30sx cement, pulled tubing to 312, circulated hole, full of cement, pulled tubing ropped off with cement 60-40 POZ 2% gel

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Clarke Corporation License No. 5105

Address P.O. Box 187, Medicine Lodge, KS 67104

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: McCoy Petroleum Corporation

STATE OF Kansas COUNTY OF Barber, ss.


Jeff Sletto

(Employee of Operator or Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts stated herein, and matters herein contained and the log of the above-described well as filed therewith, and the same are true and correct, so help me God.

(Signature) Jeff Sletto

(Address) Medicine Lodge, KS 67104



SUBSCRIBED AND SWORN TO before me this 12 day of April, 19 93

Glenda Morrison
Notary Public

My Commission Expires: Aug. 17, 1994