

15-077-21419-00-00

WELL PLUGGING RECORD
K.A.R.-82-3-117

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. MARKET, ROOM 2078
WICHITA, KS 67202

API NUMBER 15-07721419
LEASE NAME Mac Sanders
WELL NUMBER 2
4620 ft. from S Section Line
4620 ft. from E Section Line

TYPE OR PRINT
NOTICE: Fill out Completely
and return to coms. div.
office within 30 days.

SEC. 20 TWP. 31 RGE. 8 (E) or (W)
COUNTY Harper

LEASE OPERATOR ~~Jody Oil & Gas~~ R+B Oil + Gas, Inc.

ADDRESS Box 422, Attica, KS 67009

PHONE # (620) 254-7972 OPERATORS LICENSE NO. 31191

Character of well ~~Oil~~ Gas
(Oil, Gas, D&A, SWD, input, Water Supply Well)

RECEIVED
12-30-02
DEC 30 2002

Date Well Completed 12-7-01
Plugging Commenced 11/6/02
Plugging Completed 11/7/02

The plugging proposal was approved on 11/6/02 (date)
by Doug Louis KCC WICHITA (KCC District Agent's Name).

Is ACO-1 filed? yes if not, Is well log attached? not available to us N/A

Producing Formation Topeka Depth to Top 2946 Bottom 2948 T.D. 3050

Show depth and thickness of all water, oil and gas formations

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Topeka	Gas	2946	3050	8 5/8	252	none
				4 1/2	3047	2180

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set


Sanded bottom and bailed 4 sacks cement. Shot pipe at 2310, 2180, worked free. Pulled to 1300', pumped 35 sacks cement. Pulled to 800', pumped 35 sacks cement. Pulled to 300', circulated cement to surface with 60 sacks cement. Pulled rest of pipe.

Name of Plugging Contractor Quality Well Service, Inc. License No. 31925
Address 401 West Main, Lyons, KS 67554

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ~~Jody Oil & Gas~~ R+B Oil & Gas, Inc.

STATE OF Kansas COUNTY OF Harper, ss.

Randy Newberry (Employee of Operator) or (Operator) of above - described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above - described well as filled that the same are true and correct, so help me God.



(Signature) Randy Newberry
(Address) PO Box 195 Attica, KS 67009
December 20, 2002

SUBSCRIBED AND SWORN TO before me 20th day of

Rebecca S. Newberry Notary Public

My commission Expires: 7-21-05

OR