

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Comanche County. Sec. 13 Twp. 32S Rge. (E) 20 (W)

Location as "NE/CNW/SW" or footage from lines NW NE

Lease Owner Aladdin Petroleum Corporation

Lease Name Nichols Well No. 1

Office Address Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole

Date well completed 3/28 1969

Application for plugging filed 3/28 1969

Application for plugging approved 3/28 1969

Plugging commenced 3/28 1969

Plugging completed 3/28 1969

Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production None 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Warren

Producing formation None Depth to top Bottom Total Depth of Well 5390 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Mississippi	Water	5147	5390	13-3/8	499	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mud 5390' to 300'
1 sack of hulls Halliburton plug and 50 sacks cement at 300'
Mud to 40'
1 sack hulls Halliburton plug and 20 sacks cement to top of surface pipe

STATE RECEIVED
STATE CORPORATION COMMISSION
APR 9 1969
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Gabbert - Jones, Inc.
Address Sutton Place, Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgewick ss.
Leo Newlin (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.
(Signature) Leo Newlin

SUBSCRIBED AND SWORN TO before me this 8th day of April 1969
October 30, 1971 My commission expires
Virginia Parker Notary Public.

GABBENT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

NICHOLS #1
 NW NE Section 13-32S-20W
 Comanche County, Kansas

Commenced: March 5, 1969
 Completed: March 26, 1969

OPERATOR - Aladdin Petroleum Corporation

DEPTH		FORMATION	REMARKS
From	To		
0	499	Red bed and red rock	Ran 17 joints 18-3/8" casing, set @ 499' w/850 sacks cement.
499	603	Red bed and red rock	
603	672	Red bed	
672	1501	Red bed and shale	
1501	2190	Shale and shells	
2190	2283	Shale and lime	
2283	2460	Lime and shale	
2460	2574	Lime	
2574	2770	Lime and shale	
2770	2855	Lime	
2855	3409	Lime and shale	
3409	3518	Shale and lime streaks	
3518	4440	Shale and lime	
4440	4920	Lime	
4920	5025	Lime and shale	
5025	5390	Lime	
5390	TD		Dry and abandoned.

RECEIVED
 STATE CORPORATION COMMISSION
 APR 9 1969
 CONSERVATION DIVISION
 Wichita, Kansas

I, E. E. HALL, certify this is a correct copy of the Drillers' Log for the well drilled in the NW NE Section 13-32S-20W, Comanche County, Kansas, to the best of my knowledge and belief.

E. E. Hall

 E. E. HALL

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

Before me, the undersigned, a Notary Public within and for said County and State, on this 4th day of April, 1969, personally appeared E. E. Hall to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and year last above written.

My Commission Expires February 1, 1972.

Barbara J. Layton

 Barbara J. Layton, Notary Public

