


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

RUSH County. Sec. 13 Twp. 18s Rge. 17 (E) (W)
Location as "NE/CNW/SW" or footage from lines APP. C NE NE
Lease Owner PETROLEUM, INC.
Lease Name TIMKEN Well No. B-1
Office Address R.R. #2, GREAT BEND, KANSAS
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
Date well completed FEBRUARY 3 1968
Application for plugging filed FEBRUARY 3 1968
Application for plugging approved FEBRUARY 3 1968
Plugging commenced FEBRUARY 3 1968
Plugging completed FEBRUARY 3 1968
Reason for abandonment of well or producing formation NO PRODUCIBLE FORMATION

If a producing well is abandoned, date of last production NONE 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well LEO F. MASSEY
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3627 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	1005	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

HEAVY MUD TO 300', FOLLOWED BY WOODEN PLUG, PLACED 1/2 SACK HULLS AND 35 SACKS CEMENT ON TOP OF PLUG. HEAVY MUD TO 40', FOLLOWED BY WOODEN PLUG, PLACED 1/2 SACK HULLS AND 10 SACKS CEMENT ON TOP OF PLUG TO BASE OF WELL CELLAR.

RECEIVED
STATE CORPORATION COMMISSION
FEB 19 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor GARVEY DRILLING COMPANY
Address R.R. #2, GREAT BEND, KANSAS

STATE OF KANSAS, COUNTY OF BARTON, ss.
MONTE CHADD, DIST. PROD. SUPT. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Monte Chadd*
MONTE CHADD, DIST. PROD. SUPT.
R.R. #2, GREAT BEND, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 16 day of FEBRUARY, 1968

My commission expires MAY 28, 1969

Richard H. Dumber
Notary Public.

WELL LOG

COMPANY Petroleum, Inc.

SEC. 13 T. 18S R. 17W

FARM Timken 'B' NO. 1

LOC. C N/2 NE NE


TOTAL DEPTH 3627'

COUNTY Rush

COMM. 1-24-68 COMP. 2-3-68

CONTRACTOR Garvey Drilling Company

CASING 8 5/8" @ 1005' w/550 sx



ELEVATION 1951' KB

PRODUCTION D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

- 100' Clay and Sand
- 400' Sand and Red Bed
- 540' Sand
- 729' Shale
- 1001' Shale and Red Bed
- 1032' Anhydrite
- 1060' Shale and Red Bed
- 1475' Lime and Shale
- 1710' Shale and Lime
- 3049' Lime and Shale
- 3136' Lime
- 3391' Lime and Shale
- 3540' Lime
- 3585' Lime with Chert
- 3627' Lime
- 3627' RTD

RECEIVED
STATE CORPORATION COMMISSION
FEB 19 1968
CONSERVATION DIVISION
Wichita, Kansas

State of Kansas }
County of Barton } ss

I, Sam N. Stephens of Garvey Drilling Company

upon oath state the above and foregoing is a true and correct copy of the log of the Timken 'B' No. 1 well.

Sam N. Stephens

Subscribed and sworn to before me this 15th day of February 19 68

My Commission Expires: November 5th, 1969

Richard St. Boys
NOTARY PUBLIC