

15-165-30183-0000


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Rush County, Sec. 14 Twp. 18S Rge. (E) 17 (W)

Location as "NE/CNW/SW" or footage from lines C NE NE  
Lease Owner Pickrell Drilling Company  
Lease Name Kraisinger Well No. 1  
Office Address 705 4th National Bank Bldg, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed May 31 19 66  
Application for plugging filed May 31 19 66  
Application for plugging approved May 31 19 66  
Plugging commenced May 31 19 66  
Plugging completed May 31 19 66  
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo F. Massey  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3587 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	1032'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Heavy mud to 400', set plug, cemented with  
25 sacks. Heavy mud to 40', set plug.  
Cemented with 10 sacks cement to bottom of  
cellar. Plugged rat hole with 2 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION  
JUN - 9 1966  
6-9-66  
CONSERVATION DIVISION  
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Pickrell Drilling Company  
Address 705 4th National Bank Bldg, Wichita, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

C. W. SEBITS (Signature) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well at file and that the same are true and correct. So help me God.

(Signature) C. W. SEBITS  
705 4th National Bank Bldg, Wichita, Kansas  
(Address)

Subscribed and sworn to before me this 3rd day of June, 1966



My commission expires May 10, 1970

L. M. Whiting Notary Public.

15-165-30103-0000  
**ROTARY DRILLING LOG**

COMPANY: PICKRELL DRILLING COMPANY  
705 4th Natl Bank Bldg.  
Wichita, Kansas

Rotary Drilling Commenced 5-23-66

Rotary Drilling Completed 5-30-66

LOCATION: Kraisinger No. 1, C NE NE Section 14-18S-17W, Rush County, Kansas.

CONTRACTOR: **PICKRELL DRILLING COMPANY**  
Wichita, Kansas

CASING RECORD: (25 jts) 8 5/8" surface casing set at 1032', cemented with 425 sacks cement. Circulated. Completed 11:45 A.M. May 24, 1966. No oil string run, D & A.

**LOG**

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

35	Top Soil & Clay	<u>C. F. S.</u>
95	Sand	3558
225	Clay	
286	Sand	
345	Shale & Shells	<u>Slope Tests</u>
410	Shale & Sand Streaks	2400
565	Dakota Sand	2900
655	Red Beds	3400
865	Shale & Shells	
1022	Red Beds	
1059	Anhydrite	<u>S. L. M.</u>
1360	Red Beds & Shale	2781
1750	Shale & Shells	3097
2180	Lime & Shale	3412
2340	Lime	
2505	Lime & Shale	
2800	Shale	
3200	Lime & Shale	
3555	Lime	
3587	R. T. D.	

RECEIVED  
STATE CORPORATION COMMISSION  
JUN - 9 1966  
6-9-66  
CONSERVATION DIVISION  
Wichita, Kansas

The undersigned, C. W. SEBITS, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

**PICKRELL DRILLING COMPANY**

By [Signature]  
C. W. SEBITS, Attorney-in-Fact.

STATE OF KANSAS }  
COUNTY OF SEDGWICK } ss.:

On this 31<sup>st</sup> day of June, 1966, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. SEBITS, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: May 10, 1970

[Signature]  
L. M. Whiting, Notary Public