


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Take Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Locate well correctly on above
Section Plot

Rush County, Sec. 24 Twp. 18S Rge. 17W E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
C NE/4
Lease Owner Tenneco Oil Company
Lease Name PECHANEC Well No. 1-24
Office Address Ciudad Bldg, Ste. 139, 300 United Founders Blvd.
Character of Well (Completed as Oil, Gas or Dry Hole) OKC
Dry Hole

Date Well completed June 30 1980
Application for plugging filed (Verbally) June 30 1980
Application for plugging approved (Verbally) June 30 1980
Plugging commenced June 30 1980
Plugging completed June 30 1980
Reason for abandonment of well or producing formation
No commercial quantity of oil or gas
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Marion Schmidt
Producing formation Depth to top Bottom Total Depth of Well 3660'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from feet to
feet for each plug set.


T.D. 3660'

Filled hole with mud, pumped 60 sx. 50/50 posmix, 6% gel thru open end drill pipe @ 1050'.

Mud to 390', pumped 30 sx. thru drill pipe, mud to 40', $\frac{1}{2}$ sx. hulls & wood plug for solid

bridge, pumped 10 sx. to base of cellar, 5 sx. in rathole. Completed @ 3:15 a.m. 6/30/80.

Cement by Allied. State Plugger - Marion Schmidt.



(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KAW Drilling Co., Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.
K.S. Martin, President of KAW Drilling Co., Inc. (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature)

1010 Union Center, Wichita, Kansas 67202

(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of July, 19 80

My commission expires



Kathy S. Goertz
Kathy S. Goertz Notary Public.

OPERATOR: Tenneco Oil Company
CONTRACTOR: KAW Drilling Co., Inc.
WELL NAME: PECHANEC #1-24
LOCATION: C NE/4, Section 24-18S-17W
Rush County, Kansas
SPUD DATE: June 22, 1980
COMPLETION DATE: June 30, 1980

0	71	Rock
71	227	Shale
227	658	Sand & Shale
658	902	Red Beds
902	1046	Shale & Shells
1046	1062	Anhydrite
1062	1162	Shale
1162	2190	Shale & Lime
2190	2425	Shale
2425	3660	Shale & Lime
	3660	R.T.D.


Drilled 1062' of 12½" hole. Ran 26 jts. of new 8 5/8" - 24# (8rd - range 3) casing. (Talley 1047.06') Set at 1060' K.B. with 400 sx. of 50/50 posmix, 6% gel, 3% Ca.Cl. followed with 200 sx. of common cement, 3% Ca.Cl.. Plug was down at 3:15 p.m. 6-22-80. Cement by Sun.

T.D. 3660'. Filled hole with mud, pumped 60 sx. of 50/50 posmix, 6% gel, thru open end drill pipe @ 1050'. Mud to 390', pumped 30 sx. thru drill pipe, mud to 40', ½ sx. hulls & wood plug for solid bridge, pumped 10 sx. to base of cellar, 5 sx. in rathole. Completed @ 3:15 a.m. 6/30/80. Cement by Allied. State Plugger - Marion Schmidt.

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

RECEIVED
STATE CORPORATION COMMISSION
JUL 11 1980
7-11-80
CONSERVATION DIVISION
Wichita, Kansas

I, K.S. Martin, President of KAW Drilling Co., Inc., being first duly sworn on oath, state: That I have knowledge of the facts, statements and matters herein contained and that the same are true and correct.


K.S. Martin, President

Subscribed and sworn to before me on this 7th day of July, 1980.




Kathy S. Goertz, Notary Public