

LEASE NAME Pohoralek

WELL NUMBER #1
3630 Ft. from S Section Line
4290 Ft. from E Section Line

SEC. 31 TWP. 18 RGE. 17 (E) or (W)

COUNTY Rush

Date Well Completed 7-3-92

Plugging Commenced 11-14-96

Plugging Completed 12-4-96

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

COPY

LEASE OPERATOR A. L. Abercrombie, Inc.

ADDRESS Rt. #1 Box 56 Great Bend, Ks. 67530

PHONE#(316) 793-8186 OPERATORS LICENSE NO. 5393

Character of Well Oil

(Oil), Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10-16-96 (date)

by David R. Williams, Plugging Supr. (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached?

Producing Formation Arbuckle Depth to Top 3763 Bottom 3767 T.O. 3767

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Arbuckle	Oil/Water	3765	3767	8 5/8	1128'	None
				5 1/2	3765'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set. Pressure 8 5/8 to 5 1/2 Annulus PSI to 500# - held. Mix & pump 300# hulls - 25 sacks cement - 5 sacks Cel. - 110 sacks 60/40 Poz 6% Cel. Max press 2500# & shut in press 50# standing. State Rep. Richard Lacy. 12-4-96 Measure Line - Show TD @ 1050'. Dump 4.8 yards ready mix down casing. Casing loaded - Plugging complete @ 10:40 am 12-4-96

Name of Plugging Contractor A. L. Abercrombie, Inc. License No. 5393

Address Rt. #1, Box 56 Great Bend, Ks. 67530


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: A. L. Abercrombie, Inc.

STATE OF Kansas COUNTY OF Barton, ss.

E. L. Abercrombie (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) E.L. Abercrombie

(Address) Rt. #1, Box 56 Great Bend, Ks. 67530



AND SWORN TO before me this 10th day of December, 1996

Susan M. Urban Notary Public

My Commission Expires: 7-29-2000