


15-165-00064-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Biting Building  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Rush County. Sec. 12 Twp. 18 Rge. 17 (E) N (W)  
Location as "NE/CNW&SW" or footage from lines. SW SW NE  
Lease Owner Victor Drilling, Inc.  
Lease Name Grotinger Well No. 1  
Office Address 302 Koch Building, Wichita 2, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) dry hole  
Date well completed 12-24-19 53  
Application for plugging filed 12-24-19 53  
Application for plugging approved 12-24-19 53  
Plugging commenced 12-24-19 53  
Plugging completed 12-24-19 53  
Reason for abandonment of well or producing formation no commercial shows

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Warren H. Horner  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3558 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE  | PUT IN | PULLED OUT |
|-----------|---------|------|----|-------|--------|------------|
|           |         |      |    | 8 5/8 | 870    | none       |
|           |         |      |    |       |        |            |
|           |         |      |    |       |        |            |
|           |         |      |    |       |        |            |
|           |         |      |    |       |        |            |
|           |         |      |    |       |        |            |
|           |         |      |    |       |        |            |
|           |         |      |    |       |        |            |
|           |         |      |    |       |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.  
filled hole with heavy rotary mud from total depth, 3558 feet, to the surface casing, 870 feet; squeezed with 500 sacks cement and filled surface casing with cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Victor Drilling, Inc.  
Address 302 Koch Building, Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Patrick F. Gallagher (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Patrick F. Gallagher  
302 Koch Bldg., Wichita 2, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 14th day of January, 1954

John Skidmore  
Notary Public.

My commission expires December 2, 19 57

PLUGGING  
FILE SEC 12 T 18 R 17  
BOOK PAGE 4 LINE 5

24-7366-S 3-53-20M  
RECEIVED  
STATE CORPORATION COMMISSION  
1-14-54  
JAN 14 1954  
CONSERVATION DIVISION  
Wichita, Kansas

DRILLER'S LOG

Victor Drilling, Inc.

No. 1 S. Crotinger

SW SW NE 12-18-17W  
Rush County, Kansas

Ran 863' of 8 5/8" (2 1/2") smls Surface Casing

| <u>Formation</u> | <u>Depth</u> |
|------------------|--------------|
| Clay             | 55           |
| Sand             | 100          |
| Shale            | 190          |
| Shale & Sand     | 340          |
| Decota Sand      | 610          |
| Red bed          | 700          |
| Red bed          | 869          |
| Red bed & sand   | 950          |
| Red bed          | 1035         |
| Anhydrite        | 1080         |
| Shale            | 1375         |
| Shale            | 1775         |
| Shale & lime     | 1970         |
| Lime & shale     | 2120         |
| Lime & shale     | 2245         |
| Lime & shale     | 2375         |
| Lime & shale     | 2450         |
| Shale & sand     | 2490         |
| Shale            | 2600         |
| Lime & shale     | 2795         |
| Shale & lime     | 2906         |
| Shale            | 3012         |
| Shale & lime     | 3113         |
| Lime & shale     | 3202         |
| Shale & lime     | 3242         |
| Lime & shale     | 3262         |
| LKC              | 3325         |
| LKC              | 3405         |
| LKC              | 3451         |
| LKC              | 3476         |
| Lime             | 3495         |
| Cong.            | 3533         |
| Cong. & Gr. Wash | 3558         |
| Total Depth      | 3558         |

2-6-54

STATE OF INDIANA )  
 ) SS:  
County of Vanderburgh)

I, Victor R. Gallagher, declare that to the best of my knowledge, the foregoing is true.

Victor R. Gallagher  
Victor R. Gallagher

Subscribed and sworn to before me a Notary Public, this 19th day of January, 1954.

My commission expires: 9-24-56

Georgia Fischer  
Georgia Fischer, Notary Public

