

KANSAS
STATE CORPORATION COMMISSION
WELL PLUGGING SUPERVISOR'S REPORT

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ Location: CW¹/₂ NW SE
County: Rush Sec. 8 Twp. 18 Rge. 10 (E) (W) _____
Name of Field or Pool: _____ Total Depth: 3000

I have this date completed supervision of plugging of:

Well No. 1 Lease Luft-Maneth

Operator's Full Name Solar Oil Co

Complete Address: 1117 Union Natl Bldg Wichita, Kans

Plugging Contractor: Lewis Drg Co

Address: _____ License No. _____

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & A

If well is a rotary drilled dry hole did operators wait for you to arrive _____

If yes how long _____ Reason: _____

Operation Completed: Hour 9AM Day 29 Month 4 Year 58

The above well was plugged as follows:

8 5/8" at 1015' circulated with cement.
Gunned pits, circulated hole with heavy mud, set cementing plug at
500', displaced 20 sax cement through drill pipe, heavy mud to 200',
set cementing plug, 1/2 sack hulls and 20 sax cement, heavy mud to
40', set cementing plug, 1/2 sack hulls and 10 sax cement to bottom
cellar.

I hereby certify that the above well was plugged as herein stated and that I was present while the above well was being plugged.

Signed: *[Signature]*
Well Plugging Supervisor

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

Reviewed: *J. Lewis Brock*
Field Supervisor

Signed: _____ 5-6-58

Remarks:

Well Plugging Supervisor
PLUGGING
FILE SEC. 8 T. 18 R. 10
BOOK PAGE 27 LINE 37