

*10*  
KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 27 1963  
8-27-63  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Solar Oil Co  
Complete Address: 1117 Union Natl Bk Bldg Wichita, Kans  
Lease Name Betz Well No. 1  
Location NR NR NW Sec. 8 Twp. 18 Rge. (E) (W) 16  
County Rush Total Depth 3560  
Abandoned Oil Well      Gas Well x Input Well      SWD Well      D & A       
Other well as hereafter indicated:       
Plugging Contractor: Ace Pipe Pulling Co  
Address: Great Bend, Kansas License No. 2  
Operation Completed: Hour 4:30PM Day 24 Month 8 Year 63

The Above well was plugged as follows:

8 5/8" 1056' circulated with cement - 5 1/2" 3558' with 75 sax cement - perforated 3530'  
Sand back to 3520', set 4 sax cement with dump bailer - pulled 3050'  
5 1/2" casing - filled with mud to 470' - rock to 450' - filled hole  
450' to bottom cellar with ready mix cement - 6 yds.

I hereby certify that the above well was plugged as herein stated.

INVOICED  
DATE 8/29/63  
INV. NO. 9695-u

Signed: *Edson Petty*  
Well Plugging Supervisor