

KANSAS

Form CP-3  
Rev. 6-26-62

## STATE CORPORATION COMMISSION

## CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, KansasRECEIVED  
STATE CORPORATION COMMISSION

NOV 13 1967

11-13-67

CONSERVATION DIVISION  
Wichita, Kansas

GLEN N.

Operator's Full Name Glenn RupeComplete Address: 222 Brown Bldg. Wichita, KansasLease Name Foos Well No. 1Location NE NE NW Sec. 34 Twp. 17 Rge. 19 (E)    (W) XCounty Rush Total Depth 3941Abandoned Oil Well    Gas Well    Input Well    SWD Well    D & A XOther well as hereafter indicated:   Plugging Contractor: Leben Drlg. Inc.Address: Wichita, Kansas License No.   Operation Completed: Hour 3 A Day 11 Month 12 Year 1967

The Above well was plugged as follows:

RTD 3941 ~~4037~~ 8 5/8 csg set at 254' cwc

at 660'

Gunned pits, circulated heavy mud, set cementing plug and displaced 100 sc cement thru drill pipe. Heavy mud to 250' set cementing plug and displaced 25 sc cement thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: R. F. Massey  
Well Plugging SupervisorDATE 11/14/67INV. NO. 6674-W