

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 5

LOCATION C.S.E. 4

SEC. 9 TWP. 15 RGE. 16W

Dry Hole      Abandoned Oil Well      Abandoned Gas Well yes

I have today completed supervision of plugging of:

Well No. 1 Lease Schmidt

Operator Northern Natural Gas Co. Address 41310 Omaha Nebraska

Field Otis County Rush

Total Depth 35.34 Feet.

(Describe briefly the manner in which the well was plugged)

This hole had a plug at 3317 ft down solid sand  
4 ft lead was down it then 100% cement checked to  
top of plug, top 3317 ft. Then pumped cement in all  
Bradley heads down, 625 rods, set out 78 rods then pumped  
cement into Bradley head connections and got returns  
475 rods then filled 700 to top with cement. Used  
over 1200 rods cement 4 1/2 gal. all paper left in hole

H. W. Kerr  
District Conservation Agent

Date Checked OK July 21-46

REC 9 19 16W  
60 10

7-23-46  
1946

**Casing Record on Schmidt #1  
Well in C. SE/4 Section 9-18-16  
Rush County, Kansas, Otis Field**

<u>Depth</u>	<u>Size</u>	<u>Grade</u>	<u>Wt/Ft.</u>	<u>Sacks Cement</u>	<u>Estimated Fill-up of Cement</u>
94 Ft.	20"			Pulled	
405 Ft.	15 1/8"	B Lapweld	70#	90	227 Ft.
1,007 Ft.	12 1/2"	B Lapweld	50#	50	151 Ft.
2,357 Ft.	10-3/4"			Pulled	
3,235 Ft.	8-5/8"			Pulled	
3,473 Ft.	7"	C Elec. Weld	24#	40	318 Ft.
3,501 Ft.	2" Upset	Seamless	4.70#	Packer set at 3,317 Ft.*	
3,501 Ft.	1"	Ex. Heavy Line Pipe	2.17#		

\*Larkin Fig. 11 Neoseal Hook Wall Packer #7958

9 18 1620  
60 10

