

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 13 1974  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Cities Service Oil Co.  
Complete Address 209 E. William, 700 Sutton Place, Wichita, Kansas  
Lease Name Legge "A" Well No. 1  
Location SW SW NW Sec. 21 Twp. 17 Rge. (E) (W) 17  
County Rush Total Depth 4060'  
Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX  
Other well as hereafter indicated         
Plugging Contractor Duke Drilling Co.  
Address Wichita, Kansas License No.         
Operation Completed: Hour 2:30 P Day 11 Month 3 Year 1974

The above well was plugged as follows:

RTD 4060' 8 5/8 csg set at 324' owe 200 sk. Cmt. Mat. "Halibut Light"  
Gunned pits, circulated heavy mud, set cementing plug at 550' and displaced 50 sk  
cmt thru drill pipe. Heavy mud to 240' set cementing plug and displaced 25 sk cmt  
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to  
base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED  
DATE 3/18/74  
INV. NO. 8756-W

Signed: Leo J. Massey  
Well Plugging Supervisor