

15-165-20495-0000

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
FEB 14 1975
2-14-75
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Frontier Oil Company
Complete Address 1720 Wichita Plaza, Wichita, Kansas 67202
Lease Name Schmidt Well No. 11
Location NE NE SW Sec. 5 Twp. 18 Rge. (E) (W) 16
County Rush Total Depth 3555'
Abandoned Oil Well XX Gas Well XX Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Rockhold Engineering
Address Box 698, Great Bend, Kansas 67530 License No. 670
Operation Completed: Hour 11:30 A Day 12 Month 2 Year 1975

The above well was plugged as follows:

Total Depth 3555' 8 5/8 csg set at 210' cwc 135 sk.
4 1/2 csg set at 3553' cw 275 sk cem.
4 1/2 csg PBD 3020' with top perf. (2974')
Set wire line cast iron plug at 2900' - dumped 4 sk cem. W/dump bailer. (2900-2865)
Cutoff & recovered 2000' of 4 1/2 csg.
Mixed & pumped down 8 5/8 csg with with 20 sk gel & water W/300 lbs hulls, -
released plug & pumped 120 sk reg poz 6% by Allied.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo F. Massey
Well Plugging Supervisor

INVOICED

DATE 2/14/75
INV. NO. 829-W