

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 25-28LOCATION SW-SW-NWSEC. 4 TWP. 18 RGE. 16 WDry Hole Abandoned Oil Well Abandoned Gas Well Cable tool

I have this date completed supervision of plugging of:

Well No. 1 Lease HartmanOperator Cat. Bend Pipe & Supply Co. Address Box 414 Cat. Bend Kans.Field _____ County RushTotal Depth 3531 Feet.Plugging Contractor J-M Casing Pulling Co.Plugging Contractor's License No. 11Address Crest Bend Kans.

(Describe briefly the manner in which the well was plugged)

Casing in hole as follows 15" @ 480' 12 1/2" 980'
8 1/2" @ 3383 and 7" 3511 w/ 50 st Cem. Filled
hole back to 3500' w/ crushed rock and run
6 st Cem. Shot off and pulled 7" casing.

Dropped 8 1/2" in hole after parting it. Well
flowing water freely. Squeezed 12 1/2" casing w/ 400
st Cem. Also squeezed annulus between 12 and 15"
with 150 st Cem. Pumping by H.W.C.O. Job O.K.

PLUGGING

FILE SEC 4 T 18 R 16 W
BOOK PAGE 25 LINE 28

6-21-54

Warren N. Harner
District Conservation Agent

Date June 18, 1954