

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
1-12-68  
JAN 12 1968  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Shields Oil Producers, Inc.

Complete Address Russell, Kansas

Lease Name Wm Schmidt Well No. 2

Location NE SW NE Sec. 14 Twp. 17 Rge. 19 (E) (W) X

County Rush Total Depth 3925

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Co. Tools

Address \_\_\_\_\_ License No. \_\_\_\_\_

Operation Completed: Hour 3:45 A Day 11 Month 1 Year 1968

The above well was plugged as follows:

RTD 3925' 8 5/8 csg set at 255' cwc 200 sc. Cementing Material 50-50 W6%

Gunned pits, circulated heavy mud, set cementing plug at 550' and displaced 100 sc cem.

thru drill pipe. Heavy mud to 250' set cementing plug and displaced 25 sc cement thru

drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base

of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE

1/12/68  
7085-W

INV. NO.

Signed:

Leo F. Muesey  
Well Plugging Supervisor