

15-165-02121-0000

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
9-13-61
SEP 13 1961
CONSERVATION DIVISION
Wichita, Kansas

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Rush
Location: SW SE SW Sec. 22 Twp. 18 Rge. _____ (E) _____ (W) 16
Name of Field: _____ Total Depth: 3575

I have this date completed supervision of plugging of:

Lease Name: Schneider Well No. 1 SWD

Operator's Full Name: Morganstern-Specter

Complete Address: Box 661 Russell, Kansas

Plugging Contractor: Lynch Pipe Pulling Co

Address: Great Bend, Kansas License No. 396

Oil Well _____ Gas Well _____ Input Well _____ SWD Well D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 6PM Day 7 Month 9 Year 61

The above well was plugged as follows:

8 5/8" 1093' circulated with cement - 5 1/2" 3570' with 75 sax cement.

Plugs and sand to 3200', chat to 3150', set 4 sax cement with dump bailer
pulled 3090' 5 1/2" - filled hole with chunk mud to 350', set 20 sax cement
at 350', chunk mud to 150', set 20 sax cement at 150', chunk mud to
35' set roof and 10 sax cement to bottom cellar.

Signed: [Signature]
Conservation Division Agent

Reviewed: [Signature]
Field Supervisor

Remarks:

INVOICED
DATE 9/22/61
INV. NO. 3745-11